

SURVEY & REMONUMENTATION

APR 11 1995

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Approved by Menominee County
Land Survey Remonumentation
Peer Group Under Act 345 Of

P.A. Of 1990 On 12/19 19994
McGowan RLS
ACTING Chairman

For corners in
MENOMINEE
(County)

Located In: Corner Code #

1. Public Land Survey	T	33NR	27W	E-12
	T	R		
	T	R		
	T	R		
2. Property Controlling in Section	S	T	R	
	S	T	R	
3. Miscellaneous Property in Sec.	S	T	R	
	S	T	R	

RECEIVED FOR RECORD
94 DEC 12 AM 9:00
PAGE # 120 BK. 4
BARBARA MORRISON
REGISTER OF DEEDS
MENOMINEE, MI 49858

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

William Lenca

Oct. 06 94

I, _____, in a field survey on _____, 19____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

- 1848: Original Survey by John Mullett - B.T.'s - Beech, 4" - S05°E- 11 lks; Beech, 5" - N27°E- 22 lks. All original evidence for this corner has been destroyed by farming activities.
- 1975: L.C.R.C. No. 114 by George B. Wilson, RLS No. 17607, states that this corner was set by single proportionate method. A 2" dia. Alum. Pipe 30" long, magnet top & bottom, stamped Land Survey Corner RLS 17607 was set. TIES - 349' North of the centerline of the gravel driveway - 8.7' West of existing fence line - set 14" below ground surface (plow line).
- 1974: Certified Survey No. 49 by George B. Wilson shows this corner in relation to the NE and SE Corners of Section 32. It also shows the relationship of Wilson's measurement of this mile to that of A.L. Hillis' measurement in 1893.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

We found a 2" dia. Aluminum Pipe/3-1/4" diameter aluminum cap stamped "LAND SURVEY CORNER - RLS 17607" in location indicated by information contained in L.C.R.C. No. 114. The corner is near a North-South fence line with large fields on both sides and approximately 12" below the ground surface. We accepted the monument as a careful and faithful re-establishment of the position of the original corner.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Accepted 2" dia. Aluminum Pipe/3-1/4" dia. Aluminum cap stamped for corner:

5/8" x 24" Iron Rod/2" dia. Alum. cap marked "WITNESS MARKER"	N90°E	8.42 feet
5/8" x 24" Iron Rod/Ident. cap marked MI 26461/WI 1569	N38°E	14.78 feet
5/8" x 24" Iron Rod/Ident. cap marked MI 26461/WI 1569	S23°E	17.67 feet
Survey Sign Post	N90°E	8.7 feet

NOTE: All bearings are magnetic bearings. All distances are measured with steel tape. Distances to trees are to nail in side of tree.

Signed by William Lenca Date Nov. 18, 1994
Surveyor's Michigan License No. 26461