

SURVEY & REMONUMENTATION

APR 11 1995

For corners in
MENOMINEE
COMMISSION
(County)

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

Approved by Menominee County
Land Survey Remonumentation
Peer Group Under Act 345 Of
P.A. Of 1990 On 12/9 19994
McDOWD RLS
ACTING Chairman

	Located In:	Corner Code =#
1. Public Land Survey	T <u>33N</u> R <u>27W</u>	<u>F-5</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

RECEIVED FOR RECORD
94 DEC 12 AM 9:56
PAGE # 89 BK 4
BARBARA MORTISON
REGISTER OF DEEDS
MENOMINEE, MI 49855
Register of Deeds Stamp & File Number

I, William Lenca, in a field survey on June 30, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1848: Original Survey by John Mullett - B.T.'s - Cedar, 8", S86°W, 09 lks & Cedar, 9", N72°E, 18 lks. All original evidence for this corner has been destroyed by county road improvements.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No original evidence or subsequent restoration was found for this corner location. The corner was established on a straight line between corners E-5 and G-5, and in line with the centerline of a county road running south from this location. This position falls 13 feet south of an East-West County Road, and fits reasonably well with GLO distances to corners E-5 and G-5, and is accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
Set 5/8" x 24" Iron Rod/3-1/4" dia. Aluminum cap stamped for corner location:

9" dia. Tamarack	N36°E	77.15 feet	Scr. NBT
10" dia. Elm	S25°E	99.27 feet	Scr. NBT
4" dia. Maple	S39°W	68.92 feet	Scr. NBT
5" dia. Elm	N35°W	71.55 feet	Scr. NBT
Survey Sign Post	North	47.0 feet	

NOTE: All bearings are magnetic bearings. All distances are measured with steel tape. Distances to trees are to nail in side of tree.

Signed by William Lenca Date July 09, 1994
Surveyor's Michigan License No. 26461