

SURVEY & REMONUMENTATION

APR 1 1 1995

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

Approved by Menominee County
Land Survey Remonumentation
Peer Group Under Act 345 Of
P.A. of 1990 On 12/9 199 94

For corners in
MENOMINEE COMMISSION
(County)

Located In: Corner Code #

- | | | |
|------------------------------------|-----------------------------|-------------|
| 1. Public Land Survey | T <u>33</u> N R <u>27</u> W | <u>F-11</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

ACTING
CHAIRMAN
BARBARA MORRISON
REGISTER OF DEEDS
MENOMINEE, MI 49858

RECEIVED FOR RECORD
94 DEC 12 AM 9:00

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	13	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						

William Lenca in a field survey on **May 26**, 19 **94**

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
- 1848: Original Survey by John Mullett - B.T.'s - Birch, 18" - S04°W - 33 lks; Sugar, 8" - N19°E - 25 lks. All original evidence for this corner has been destroyed by County Road improvements.
 - 1984: In a survey of the North Line of Sections 32 and 33, we established this corner in the centerline of a county road running West and in line with old fence lines running North - South and East. We set a 1/2" x 24" iron rod with a plastic identification cap and established the following B.T.'s: 12" Cherry - S78°W - 125.85'; 5" W. Pine - N04°W - 38.05'; 5" Cherry - S32°E - 43.35'; 3" Aspen - S89°E - 37.45'.
 - 1987: Certified Survey No. 519 by William Lenca, RLS No. 26461, uses this corner as a control for a survey in Sections 27, 28, 33 and 34. The corner monument is not described, however, we used the corner described above.

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
- We found a 1/2" diameter iron rod in the centerline of a gravel road running West, and in line with old fences running North - South and East from this location. We also found the B.T.'s established in 1984, and mentioned in part "A". This corner has been used for control in several surveys over the past 10 years, and is accepted as the best available evidence of the position of the original corner.



- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- Set 2-1/2" x 30" Alum. Pipe/3-1/4" dia. Alum. cap stamped for corner location:
- | | | | |
|--|-------|-------------|----------|
| 12" dia. White Pine | N06°W | 37.86 feet | Scr. NBT |
| 5/8" x 24" Iron Rod/2" dia. Alum. cap (WITNESS MARKER) | S88°E | 33.00 feet | |
| 7" dia. Cherry | S21°E | 54.90 feet | Scr. NBT |
| 12" dia. Cherry | S76°W | 126.24 feet | Scr. NBT |
| Survey Sign Post | S88°E | 33.3 feet | |

NOTE: All bearings are magnetic bearings. All distances are measured with steel tape. Distances to trees are to nail in side of tree.

Signed by William Lenca Date Nov. 18, 1994
Surveyor's Michigan License No. 26461

122