

SURVEY & REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Approved by Menominee County
Land Survey Remonumentation
Peer Group Under Act 345 Of
P.A. Of 1990 On 12/9 19994
ALTA Chairman

For corners in MENOMINEE APR 11 1995

(County)

COMMISSION

Located In: Corner Code #

- | | | |
|------------------------------------|---------------------------|------------|
| 1. Public Land Survey | T <u>33N</u> R <u>27W</u> | <u>G-3</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

RECEIVED FOR RECORD
94 DEC 12 AM 8:56
PAGE # 88 BK 4
BARBARA MORRISON
REGISTER OF DEEDS
MENOMINEE, MI 49858
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1					
3											
4	7	8	9	10	11	12					
5											
6	18	17	16	15	14	13					
7											
8	19	20	21	22	23	24					
9											
10	30	29	28	27	26	25					
11											
12	31	32	33	34	35	36					
13											

I, William Lenca, in a field survey on June 09, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1848: Original Survey by John Mullett - B.T.'s - Cedar, 10", N21°E, 13 lks & Cedar, 12", S78°W, 18 lks. No evidence of the original corner or its accessories was found.
1977: L.C.R.C. No. 166 recorded by George B. Wilson, RLS No. 17607, states that a 4 inch square concrete monument was set based on remnants of old fences as the best available evidence. No. B.T.'s are given.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A 4 inch square concrete monument as described in L.C.R.C. No. 166 (mentioned in part "A"). This corner location falls 28 feet South of the centerline of an East - West County Road. This corner has been used for survey control over the past 17 years, and is accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
Accepted the 4" square concrete monument - Set 3-1/4" dia. Alum. cap stamped for corner:

18" dia. Tamarack	N50°E	76.32 feet	Scr. NBT
5" dia. Cedar	S47°E	18.00 feet	Scr. NBT
5" dia. Maple	S09°E	36.28 feet	Scr. NBT
12" dia. Tamarack	S51°W	22.59 feet	Scr. NBT
Survey Sign Post	South	2.5 feet	

NOTE: All bearings are magnetic bearings. All distances are measured with steel tape. Distances to trees are to nail in side of tree.

Signed by William Lenca Date July 09, 1994
Surveyor's Michigan License No. 26461