

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

Approved by Menominee County  
Land Survey Remonumentation  
Peer Group Under Act 345 Of

P.A. Of 1990 On 12/16 1996

For corners in

<u>MENOMINEE</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>33</u> N R <u>27</u> W	<u>G08</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

Chairman  
Mc Davis RLS

DEC 20 AM 9:35

RECEIVED FOR RECORD

# 396, BK 4

WILBATA MORGANSON  
REGISTERED LAND SURVEYOR

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, William Lenca, in a field survey on Sep 10, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5			4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21	●	22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

- 1848: Original Survey by John Mullett - B.T.'s - Hemlock, 8" - S28°W - 10 lks; Hemlock, 12" - N60°W - 15 lks. All original evidence for this corner has been destroyed by logging operations and private road construction.
- 1984: L.C.R.C. No. 598 by George B. Wilson, RLS No. 17607, states "no orig. evidence found - used old fenceline E - W and testimony of Emil Danielson." Set HDR Alum. Berntsen Mon. - TIES: Deep-1 Magnets - North 2 feet & East 2 feet.
- 1983: Certified Survey No. 373 by George B. Wilson, RLS No. 17607, shows this corner as it relates to other corners in Sections 15 & 22 (Sec. Subd.'s).

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

We found a 3/4 inch diameter aluminum rod with a 3-1/4 inch diameter aluminum cap in proper location as indicated by measurements recorded in Certified Survey No. 373. This corner has been used by local surveyors for control in several surveys in this area, and is accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
Accepted existing 3/4" dia. Aluminum Rod/3-1/4" dia. Alum cap stamped for corner location:

18" dia. Norway Pine	N73°E	31.22 feet	Scr. NBT
10" dia. Tamarack	S52°E	50.52 feet	Scr. NBT
10" dia. White Pine	S64°W	68.77 feet	Scr. NBT
8" dia. Cedar	N42°W	12.25 feet	Scr. NBT
Metal Survey Sign Post	North	1.9 feet	

NOTE: All bearings are magnetic bearings. All distances are measured with steel tape. Distances to trees are to nail in side of tree.

Signed by William Lenca  
Surveyor's Michigan License No. 26461

Date Nov. 21, 1996

