

SURVEY & REMONUMENTATION

Approved by Menominee County
Land Survey Remonumentation
Peer Group Under Act 345 Of

P.A. Of 1990 On 12/9 199 94

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in APR 1 1 1995
MENOMINEE
(County) **COMMISSION**

Del Davis
ACTING Chairman

	Located In:	Corner Code #:
1. Public Land Survey	T <u>33N</u> R <u>27W</u>	<u>G-09</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

RECEIVED FOR RECORD

94 DEC 12 AM 9:00

PAGE # 123 BK 4

BARBARA MORRISON
REGISTER OF DEEDS
MENOMINEE MI 49858

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

William Lenca May 11 94

I, _____, in a field survey on _____, 19 _____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
- 1848: Original Survey by John Mullett - B.T.'s - Hemlock, 14" - S44°E - 09 lks; Birch, 12" - S25°W - 11 lks. All original evidence for this corner has been destroyed by County Road improvements.
 - 1987: L.C.R.C. No. 750 by William Lenca, RLS No. 26461, states that a 5/8" x 24" Iron Rod/Ident. cap marked "MI 26461/WI 1569 was set in the centerline of County Roads E - W and S. and in line with old fence North. New B.T.'s - Power Pole - N10°E - 34.11 feet; center of 6" dia. Iron Post - S34°E - 47.78 feet; Spruce, 24" - S48°W - 70.22 feet.

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
- We recovered the 5/8" x 24" Iron Rod and B.T.'s as described in L.C.R.C. No. 750. The corner position falls in the centerline of county roads running East - West and South from this location, and in line with an old fence running North. This corner has been used for control in several surveys in the area, and is accepted as the best available evidence of the position of the original corner.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- Set 5/8" x 24" Iron Rod/3-1/4" dia. Alum. cap stamped for corner location in Monument Box:
- | | | |
|--|-------|------------|
| 5/8" x 24" Iron Rod/2" dia. Alum. cap (WITNESS MARKER) | N25°E | 94.58 feet |
| 5/8" x 24" Iron Rod/2" dia. Alum. cap (WITNESS MARKER) | S35°E | 46.08 feet |
| 5/8" x 24" Iron Rod/2" dia. Alum. cap (WITNESS MARKER) | S30°W | 47.90 feet |
| 5/8" x 24" Iron Rod/2" dia. Alum. cap (WITNESS MARKER) | N05°W | 36.07 feet |
| Survey Sign Post | N05°W | 37.0 feet |

NOTE: All bearings are magnetic bearings. All distances are measured with steel tape. Distances to trees are to nail in side of tree.

Signed by William Lenca Date Nov. 18, 1994

Surveyor's Michigan License No. 26461

123