

SURVEY & REMONUMENTATION

APR 11 1995

COMMISSION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

Approved by Menominee County
Land Survey Remonumentation
Peer Group Under Act 345 Of

P.A. Of 1990 On 12/9 199 94

McL Davis RLS
ACTING Chairman

For corners in MENOMINEE <small>(County)</small>	Located In:	Corner Code ##
1. Public Land Survey	T <u>33N</u> R <u>27W</u>	<u>G-10</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

RECEIVED FOR RECORD
94 DEC 12 AM 9:00
PAGE # 184 BK 4
BARBARA MORRISON
REGISTER OF DEEDS
MENOMINEE, MI 49853
Register of Deeds Stamp # _____ File Number _____

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

William Lenca

Jun 29 19 94

I, _____, in a field survey on _____, 19 _____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1848: Original Survey by John Mullett - B.T.'s - Tamarack, 8" - S26°E - 11 lks; Spruce, 7" - N39°E - 12 lks. All original evidence for this corner has been destroyed by logging activities.
- 1987: L.C.R.C. No. 751 by William Lenca, RLS No. 26461, states that a 3/4" x 60" Alum. Rod/3-1/4" Alum. cap was set in line with old fence to the north. North-South position was established by doubling distance between NW Corner and 1/16 line fence. New B.T.'s - 6" W. Ash - N12°E - 20.01'; Tamarack, 8" - S83°E - 16.78'; W. Ash, 9" - S25°W - 25.62'; W. Ash, 9" - N70°W - 13.42'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

We recovered the 3/4" x 60" Aluminum Rod/3-1/4" dia. Aluminum cap and B.T.'s as described in L.C.R.C. No. 751. The corner falls in line with an old fence running North from this location and at a distance South of the NW Corner of Section 27, which matches the well defined 1/16 line to the north. This corner position has been used for control for several surveys in the area, and is accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Accepted 3/4" x 60" Alum. Rod/3-1/4" dia. Alum. cap stamped for corner location:

8" dia. White Ash - (Ex. B.T.)	N12°E	20.01 feet	Scr. NBT
9" dia. Tamarack - (Ex. B.T.)	S83°E	16.78 feet	Scr. NBT
9" dia. White Ash - (Ex. B.T.)	S25°W	25.62 feet	Scr. NBT
9" dia. White Ash - (Ex. B.T.)	N70°W	13.42 feet	Scr. NBT
Survey Sign Post	South	1.0 feet	

NOTE: All bearings are magnetic bearings. All distances are measured with steel tape. Distances to trees are to nail in side of tree.

Signed by William Lenca Date Nov. 21, 1994
Surveyor's Michigan License No. 26461

124