

# SURVEY & REMONUMENTATION

APR 1 1 1995

COMMISSION

## LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

Approved by Menominee County  
Land Survey Remonumentation  
Peer Group Under Act 345 Of  
P.A. of 1990 On 12/9 199 94

*Mr. Davis RLS*  
ACTING Chairman  
PAGE # 125 BK 4  
BARBARA MORRISON  
REGISTER OF DEEDS  
MENOMINEE, MI 49858  
DEC 12 AM 9:00  
RECEIVED FOR RECORD

For corners in  
MENOMINEE  
(County)

Located In:

Corner Code #

1. Public Land Survey	T <u>33N</u> R <u>27W</u>	_____ <u>G-11</u> _____
	T _____ R _____	_____ _____
	T _____ R _____	_____ _____
	T _____ R _____	_____ _____
2. Property Controlling in Section	S _____ T _____ R _____	_____ _____
	S _____ T _____ R _____	_____ _____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____ _____
	S _____ T _____ R _____	_____ _____

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

William Lenca Mar. 25 1994

I, \_\_\_\_\_, in a field survey on \_\_\_\_\_, 19\_\_\_\_, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

- 1848: Original Survey by John Mullett - B.T.'s - Beech, 3" - S56°W - 16 lks; Beech, 12" - N48°E - 48 lks. No original evidence for this corner was recovered.
- 1979: L.C.R.C. No. 197 by George B. Wilson, RLS No. 17607, states that a 4" square concrete monument 36" long, pin in center, was set using double proportionate method. TIES: 24" Beech - 3.10' - 350 deg azm; 35" Beech - 17.90' - 25 deg azm.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

We recovered the 4" square concrete monument and 2 Beech B.T.'s as described in L.C.R.C. No. 197. This corner has been used as control in several surveys over the past 15 years, and is accepted as a careful and faithful re-establishment of the position of the original corner.



**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

Set 3-1/4" dia. Aluminum cap on 1/2" dia. Iron Rod in existing 4" square concrete monument:

26" dia. Beech	N10°W	3.85 feet	Scr. NBT
4" dia. Beech	S78°E	28.26 feet	Scr. NBT
5" dia. Tamarack	S18°W	39.62 feet	Scr. NBT
6" dia. White Birch	S88°W	35.82 feet	Scr. NBT
Survey Sign Post	East	1.9 feet	

**NOTE: All bearings are magnetic bearings. All distances are measured with steel tape. Distances to trees are to nail in side of tree.**

Signed by William Lenca Date Nov. 21, 1994  
Surveyor's Michigan License No. 26461

125