

SURVEY & REMONUMENTATION COMMISSION

APR 11 1995

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Approved by Menominee County
Land Survey Remonumentation
Peer Group Under Act 345 Of

P.A. Of 1990 On 12/9 199 94

For corners in
MENOMINEE
(County)

Located In:

Corner Code ≠#

- | | | |
|------------------------------------|---------------------------|-------------|
| 1. Public Land Survey | T <u>33N</u> R <u>27W</u> | <u>G-12</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

ACTING Chairman
BARBARA MORRISON
REGISTER OF DEEDS
MENOMINEE MI 49853

RECEIVED FOR RECORD
DEC 12 AM 9:00
GE # 126 BK 4

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	N
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

William Lenca

May 11

94

I, _____, in a field survey on _____, 19 _____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1848: Original Survey by John Mullett - B.T.'s - Hemlock, 30" - N41°W - 04 lks; Hemlock, 24" - S20°E - 25 lks. No original evidence for this corner was recovered.

1979: L.C.R.C. No. 204 by George B. Wilson, RLS No. 17607, states that a 4" square concrete monument 12" long was set in road of gravel pit by single proportionate method. No new ties to the corner are given.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

We recovered the 4" square concrete monument as described in L.C.R.C. No. 204. The corner monument falls midway and on line between the NW Corner and the SW Corner of Section 34. This corner has been used for control for surveys in the area over the past 15 years, and is accepted as a careful and faithful re-establishment of the position of the original corner.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Accepted existing 4" square concrete monument:

6" dia. Cedar	N78°E	50.42 feet	Scr. NBT
22" dia. White Pine	S11°W	39.49 feet	
12" dia. White Ash	S61°W	86.61 feet	Scr. NBT
7" dia. Hemlock	N20°W	37.45 feet	Scr. NBT
Survey Sign Post	N05°E	15.3 feet	

NOTE: All bearings are magnetic bearings. All distances are measured with steel tape. Distances to trees are to nail in side of tree.

Signed by William Lenca Date Nov. 21, 1994
Surveyor's Michigan License No. 26461