

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Approved by Menominee County
Land Survey Remonumentation
Peer Group Under Act 345 Of
P.A. of 1990 On 12/12 1996
W. Lenca Chairman

For corners in
MENOMINEE
(County)

Located In: Corner Code #

1. Public Land Survey T33N R27W H01
T R
T R
T R

2. Property Controlling in Section S T R
S T R
S T R

3. Miscellaneous Property in Sec. S T R
S T R

95 DEC 20 AM 9:37
REGISTER OF DEEDS
MENOMINEE COUNTY
422 BC 5

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____
SAME AS CORNER H-13 T34N-R27W

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	10		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

I, William Lenca, in a field survey on Nov 13, 1996, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1847: Original Survey (Twp Bdy) by James H. Mullett - B.T.'s - Spruce, 4" - N23°E - 17 lks; Tamarack, 10" - N51°W - 29 lks. All original evidence for this corner has been destroyed by logging activities.
- 1984: Certified Survey No. 381, recorded by George B. Wilson, RLS No. 17607, shows this corner as it relates to other corners in Section 3, T33N-R27W. The corner monument is not described and no B.T.'s are given.
- 1991: L.C.R.C. No. 911, Book 3, recorded by William Lenca, RLS No. 26461, states "Found Standard Menominee County Survey Marker set by George B. Wilson, RLS No. 17607, as established and recorded in Certified Survey No. 381." B.T.'s - 5" Elm - N66°E - 10.41'; 3" W. Ash - S04°W - 23.29'; 5" W. Ash - S52°W - 13.65'; 3" W. Ash - S81°W - 22.2'; Carsonite - S50°E - 1.32'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

In a retracement of the North Line of Section 3, T33N-R27W, we found a 3/4 inch diameter aluminum rod with a 3-1/4 inch diameter aluminum cap (described as Standard Menominee County Survey Marker in L.C.R.C. No. 911) in a location matching that recorded in Certified Survey No. 381. We also found the 4 B.T.'s as described in L.C.R.C. No. 911 (see part "A"). This corner location has been used for control in several surveys in this area, and is accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
Accepted existing 3/4" dia. Alum. Rod 5' long/3-1/4" dia. Alum. cap stamped for corner location:

5" dia. Elm	N66°E	10.41 feet	Scr. NBT
3" dia. White Ash	S04°W	23.29 feet	Scr. NBT
5" dia. White Ash	S52°W	13.65 feet	Scr. NBT
6" dia. Elm	N33°W	53.48 feet	Scr. NBT
Carsonite	S56°E	1.32 feet	



NOTE: All bearings are magnetic bearings. All distances are measured with steel tape. Distances to trees are to nail in side of tree.

Signed by William Lenca Date Nov. 20, 1996
Surveyor's Michigan License No. 26461

422