

SURVEY & REMONUMENTATION

FEB 11 1998

Approved by Menominee County
Land Survey Remonumentation
Four Group Under Act 345 Of
P.A. of 1986 On 12/30, 1997
Mike Davis RLS
Chairman

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in
MENOMINEE
(County)

Located In:	Corner Code #
T <u>33</u> N R <u>27</u> W	H-07
T ___ R ___	_____
T ___ R ___	_____
T ___ R ___	_____
S ___ T ___ R ___	_____
S ___ T ___ R ___	_____
S ___ T ___ R ___	_____

- Public Land Survey
- Property Controlling in Section
- Miscellaneous Property in Sec.

RECEIVED FOR RECORDING
97 DEC 30 PM 4:05
PAGE # 629 RLS
BARBARA MORRISON
REGISTER OF DEEDS
MICHIGAN, 48863

Register of Deeds Stamp & File Number

- Lot No. _____, Recorded Plat _____
- Private Claims _____

I, William Lenca, in a field survey on Dec. 12, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

- 1848: Original Survey by John Mullett - B.T.'s - Cedar, 4" - S44°E - 18 lks.; Cedar, 4" - N63°E - 10 lks. All original evidence for this corner has been destroyed by logging activities.
- 1900: Albert Hass's survey of Section 15 states "3" cedar post formerly set from Government B.T.
- 1976: L.C.R.C. No. 123 by George B. Wilson, RLS No. 17607, states Based on prop. measure from survey by Albert Hass, and on very old blazes & on Prop. meas. from old fence lines, all ob which correspond favorably with each other. Could find no evidence of orig. BTs. Set 2" x 30" alum. pipe/stamped cap. WITs: 4" ash - 184° azm - 7.5'; 3" ash - 122°azm - 5.8'; 3" ash - 78° azm - 8.1'
- 1976: Certified Survey Number 373 by George B. Wilson, RLS No. 17607, shows this corner in relation to other corners in Section 15 and 22, T33N-R27W.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

After computing the location of this corner based on Geroge Wilson's surveys in Section 15 and 22, we traversed in to it and recovered a 2 inch diameter aluminum pipe with a 3-1/4 inch diameter aluminum cap stamped "RLS 17607 - 1976". We also found 3 bearing trees as described in L.C.R.C. No. 123 (see part A). This position fits very closely with Albert Hass' Survey, has been used by local surveyors for more than 20 years, and is accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Accepted existing 2" dia. Aluminum Pipe/3-1/4" dia. Alum cap stamped for corner location:

4" dia. Maple	N07°W	8.31 feet	Scr. NBT
8" dia. Maple	S72°E	24.34 feet	Scr. NBT
6" dia. White Ash	S05°W	35.49 feet	Scr. NBT
5" dia. White Ash	S79°W	21.26 feet	Scr. NBT
Metal Survey Sign Post	North	1.0 feet	



NOTE: All bearings are magnetic bearings. All distances are measured with steel tape. Distances to trees are to nail in side of tree.

Signed by William Lenca
Surveyor's Michigan License No. 26461

Date Dec. 29, 1997