

SURVEY & REMONUMENTATION

Approved by Menominee County
Land Survey Remonumentation
Peer Group Under Act 345 Of
P.A. Of 1990 On 12/9 19994
McDANIS RLS
Chairman

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

APR 11 1995
For corners in
MENOMINEE
COMMISSION
(County)

Located in: _____ Corner Code -# _____

- | | | |
|------------------------------------|---------------------------|-------------|
| 1. Public Land Survey | T <u>33N</u> R <u>27W</u> | <u>H-09</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

RECEIVED FOR RECORD
94 DEC 12 AM 9:00
PAGE # 127 BK 4
BARBARA MORRISON
REGISTER OF DEEDS
MENOMINEE MI 48852
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1					
3											
4	7	8	9	10	11	12					
5											
6	18	17	16	15	14	13					
7											
8	19	20	21	22	23	24					
9											
10	30	29	28	27	26	25					
11											
12	31	32	33	34	35	36					
13											

William Lenca May 11 1994
I, _____, in a field survey on _____, 19____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
1848: Original Survey by John Mullett - B.T.'s - Birch, 6" - S54°W - 12 lks; Birch, 15" - N37°E - 09 lks. All original evidence for this corner has been destroyed by county road improvements.
1982: L.C.R.C. No. 543 by William Lenca, RLS No. 26461, states that a P.K. nail was found in the centerline of county roads East - West and North and in line with an old fence South. No other evidence was found. Replaced the P.K. Nail with a Railroad Spike. New B.T.'s - Power Pole - N45°E - 35.68'; W. Birch, 6" - S46°E - 62.75'; Power Pole - S86°W - 165.25'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
We recovered the Railroad Spike and B.T.'s as described in L.C.R.C. No. 543. The corner falls in the centerline of county roads running East - West and North from this location, and in line with an old fence line running South. This corner has been used as control for several surveys over the past 12 years, and is accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
Set 5/8" x 24" Iron Rod/3-1/4" dia. Aluminum cap stamped for corner in Monument Box:

5/8" x 24" Iron Rod/2" Alum. cap marked "WITNESS MARKER"	N43°E	48.32 feet	
6" dia. White Birch	S46°E	62.75 feet	Scr. NBT
36" dia. White Pine	S00°W	34.58 feet	Scr. NBT
6" dia. White Pine	N42°W	109.15 feet	Scr. NBT
Survey Sign Post	S05°W	33.0 feet	

NOTE: All bearings are magnetic bearings. All distances are measured with steel tape. Distances to trees are to nail in side of tree.

Signed by William Lenca Date Nov. 21, 1994
Surveyor's Michigan License No. 26461

127