

**SURVEY & REMONUMENTATION**

APR 11 1995

**COMMISSION**

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

Approved by Menominee County  
Land Survey Remonumentation  
Peer Group Under Act 345 Of  
P.A. of 1990 On 12/9 199 94  
*Mel Davis RLS*  
Chairman

For corners in

MENOMINEE  
(County)

Located In:

Corner Code #

- |                                    |                           |             |
|------------------------------------|---------------------------|-------------|
| 1. Public Land Survey              | T <u>33N</u> R <u>27W</u> | <u>H-11</u> |
|                                    | T _____ R _____           | _____       |
|                                    | T _____ R _____           | _____       |
|                                    | T _____ R _____           | _____       |
| 2. Property Controlling in Section | S _____ T _____ R _____   | _____       |
|                                    | S _____ T _____ R _____   | _____       |
| 3. Miscellaneous Property in Sec.  | S _____ T _____ R _____   | _____       |
|                                    | S _____ T _____ R _____   | _____       |

RECEIVED FOR RECORD  
4 DEC 12 AM 9:00  
Chairman  
BARBARA MORRISON  
REGISTER OF DEEDS  
MENOMINEE MI 49958

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L	I
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	16	17	18	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

William Lenca

Mar. 22

94

I, \_\_\_\_\_, in a field survey on \_\_\_\_\_, 19 \_\_\_\_\_, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

- 1848: Original Survey by John Mullett - B.T.'s - Tamarack, 10" - N10°W - 12 lks; Tamarack, 10" - S60°W - 36 lks. No original evidence for this corner was recovered.  
1979: L.C.R.C. No. 199 by George B. Wilson, RLS No. 17607, states that a 4" square x 36" long concrete monument, 1/2" pin in center was set by single proportion method. New B.T.'s - 12" Hemlock - 9.30 feet - 180 deg azm; 10" Hemlock - 8.70 feet - 332 deg azm; 10" Hemlock - 7.50 feet - 18 deg azm; 12" Hemlock - 6.00 feet - 96 deg azm.  
1979: Certified Survey No. 171 by George B. Wilson, RLS No. 17607, shows a section subdivision of Section 34, and shows corner H-11 as it relates to other corners in the section. The corner monument is described as a 4" square concrete monument 36" long, 1/2" pin in center.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

We recovered the 4" square concrete monument and 4 Hemlock B.T.'s as described in L.C.R.C. No. 199. Since there are no old fences or signs of well defined occupation, and since this corner has been used as control for several surveys in the area, it is accepted as a careful and faithful re-establishment of the position of the original corner.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

Set 3-1/4" dia. Aluminum cap stamped for corner on existing 4" square concrete monument:

8" dia. Tamarack	N12°E	18.27 feet	Scr. NBT
5" dia. Tamarack	N87°E	17.55 feet	Scr. NBT
12" dia. Tamarack	S05°W	9.13 feet	Scr. NBT
12" dia. Tamarack	S27°W	28.22 feet	Scr. NBT
Survey Sign Post	N20°E	2.3 feet	

**NOTE: All bearings are magnetic bearings. All distances are measured with steel tape. Distances to trees are to nail in side of tree.**

Signed by William Lenca Date Nov. 21, 1994  
Surveyor's Michigan License No. 26461

128