

SURVEY & REMONUMENTATION

APR 1 1 1995

COMMISSION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

Approved by Menominee County
Land Survey Remonumentation
Peer Group Under Act 345 OF
P.A. OF 1988 On Dec 16 1994
Mr. Davis RLS

For corners in
MENOMINEE
(County)

Located In: Corner Code #

1. Public Land Survey	T <u>33N</u> R <u>27W</u>	<u>J-11</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

RECEIVED FOR RECORD
94 DEC 27 AM 10:47
PAGE # 180 BK 4
BARBARA MORRISON
REGISTER OF DEEDS
MENOMINEE MI 49358

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, William Lenca, in a field survey on Mar. 25, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1848: Original Survey by John Mullett - B.T.'s - Cedar, 8" - S17°E - 10 lks; Cedar, 10" - S60°W - 10 lks. All original evidence for this corner has been destroyed by county road improvements.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

We recovered a 1/2" diameter iron rod in the centerline of a East - West County Road, 10' West of the centerline of a county road running North, and in line with a very old fence line running South from this location. This position fits well with long standing lines of occupation to the East, and has been used for control in surveys in the area for several years. We therefore accepted the position of the iron rod as the best available evidence of the position of the original corner.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 3-1/4" dia. Aluminum cap stamped for corner location on existing 1/2" dia. iron rod:

9" dia. Cedar	N16°E	158.31 feet	Scr. NBT
6" dia. Maple	S21°E	62.08 feet	Scr. NBT
5" dia. Cedar	S59°W	66.96 feet	Scr. NBT
4" dia. Cedar	N40°W	68.53 feet	Scr. NBT
Survey Sign Post	S01°W	34.7 feet	

NOTE: All bearings are magnetic bearings. All distances are measured with steel tape. Distances to trees are to nail in side of tree.

Signed by William Lenca Date Nov. 29, 1994

Surveyor's Michigan License No. 26461