

# SURVEY & REMONUMENTATION

APR 11 1995

COMMISSION

## LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

Approved by Menominee County  
Land Survey Remonumentation  
Peer Group Under Act 345 Of  
P.A. Of 1990 On 12/19 19994  
McL Davis RLS  
ACTING Chairman

For corners in MENOMINEE (County)

	Located In:	Corner Code #
1. Public Land Survey	T <u>33N</u> R <u>27W</u>	<u>K-09</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

RECEIVED FOR RECORD  
 94 DEC 12 AM 9:01  
 PAGE # 134 BK 4  
 BARBARA MORRISON  
 REGISTER OF DEEDS  
 MENOMINEE MI 49888

Register of Deeds Stamp & File Number

I, William Lenca, in a field survey on Mar. 31, 1994

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

**A. Description of original monument and accessories and/or subsequent restoration:**

- 1848: Original Survey by John Mullett - B.T.'s - Cedar, 5" - N46°E - 06 lks; Cedar, 5" - N42°W - 10 lks. All original evidence for this corner has been destroyed by farming activities.
- 1990: Survey and subdivision of Section 25, T33N-R27W by William Lenca, RLS 26461 - notes state that a 5/8" dia. x 24" iron rod/Ident. cap was set at an old squared fence post, 8" square. New B.T.'s: 6" dia. Elm - N80°E - 79.38 feet; 6" dia. Tam. - S13°W - 8.05 feet; 8" dia. Tam. - N51°W - 35.91 feet; 12" dia. Tam. - N12°W - 22.90 feet.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

We recovered the 5/8" dia. x 24" iron rod at an old squared fence post 8 inches square, and 4 B.T.'s as described in part "A". There are old fences running North and East from this location. This position also fits well with a GLO terrain call to a swamp edge to the west 3.46 chains, and is accepted as the best available evidence of the position of the original corner.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

Set 2-1/2" Alum. Pipe 30" long/3-1/4" dia. Aluminum cap stamped for corner location:

6" dia. Elm (Ex. B.T.)	N80°E	79.38 feet	Scr. NBT
7" dia. Tamarack (Ex. B.T.)	S13°W	8.05 feet	Scr. NBT
8" dia. Tamarack (Ex. B.T.)	N51°W	35.91 feet	Scr. NBT
12" dia. Tamarack (Ex. B.T.)	N12°W	26.90 feet	Scr. NBT
Carsonite Marker	S27°W	0.7 feet	

**NOTE: All bearings are magnetic bearings. All distances are measured with steel tape. Distances to trees are to nail in side of tree.**

Signed by William Lenca Date Nov. 29, 1994

Surveyor's Michigan License No. 26461

134