

P.A. Of 1990 On 12/20 19995
Mr. Sami RLS
Chairman

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

MENOMINEE
(County)

Located in:

Corner Code #

- | | | |
|------------------------------------|---|-------------|
| 1. Public Land Survey | T <u>33</u> N R <u>27</u> W | <u>L-5</u> |
| | T <u> </u> R <u> </u> | <u> </u> |
| | T <u> </u> R <u> </u> | <u> </u> |
| | T <u> </u> R <u> </u> | <u> </u> |
| 2. Property Controlling in Section | S <u> </u> T <u> </u> R <u> </u> | <u> </u> |
| | S <u> </u> T <u> </u> R <u> </u> | <u> </u> |
| 3. Miscellaneous Property in Sec. | S <u> </u> T <u> </u> R <u> </u> | <u> </u> |
| | S <u> </u> T <u> </u> R <u> </u> | <u> </u> |

REGISTERED FOR RECORD
95 DEC 27 PM 3:29
PAGE 268 BK 4
BARBARA MORGANSON
REGISTERED DEEDS
MENOMINEE COUNTY

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, William Lenca, in a field survey on Aug. 17, 1995 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L
1											
2	6		5		4		3		2		1
3											
4	7		8		9		10		11		12
5											
6	13		17		16		15		14		13
7											
8	19		20		21		22		23		24
9											
10	30		29		28		27		26		25
11											
12	31		32		33		34		35		36
13											

A. Description of original monument and accessories and/or subsequent restoration:

- 1848: Original Survey by John H. Mullett - B.T.'s - W. Ash, 14", S41°E, 43 lks. Hemlock, 36", N40°W, 35 lks. All original evidence for this corner has been destroyed by logging activities.
1902: Record of Survey by Albert Haas, County Surveyor, shows partial subdivision of Section 12 and shows the location of corner L-3 as it relates to other corners in Section 12. Haas' record states that "corner formerly set". No monument is described and no new ties are given.
1984: L.C.R.C. No. 596 by George B. Wilson, RLS No. 17607, states a HDR Monument/4" dia. Alum. cap was set from fence lines. TIES: Deep-1 - 2' North & 2' East.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 3/4" x 60" Alum. Rod/3-1/4" dia. Alum. cap 33 feet North of old East- West fence as described in L.C.R.C. No. 596. This fence runs on South side of an East - West county road 1/4 mile to the East of this corner. There is also an ancient fence running South from this corner. Our measured distance East to the SE Corner of Section 12 is 2638.88 feet, compared to Albert Haas' record distance of 2645.3 feet. This corner has been used by local surveyors for at least 12 years, and is accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
Accepted 3/4" dia. x 60" Alum. Rod/3-1/4" dia. Alum. cap stamped for corner location:

6" dia. W. Ash	S82°E	22.25 feet	Scr. NBT
30" dia. w. Pine	S07°W	37.08 feet	Scr. NBT
12" dia. W. Pine	S87°W	44.97 feet	Scr. NBT
6" dia Maple	North	12.21 feet	Scr. NBT
Metal Survey Sign Post	N15°E	1.3 feet	



NOTE: All bearings are magnetic bearings. All distances are measured with a steel tape. Distances to trees are to nail in side of tree.

Signed by William Lenca
Surveyor's Michigan License No. 26461

Date Nov. 24, 1995