

**SURVEY & REMONUMENTATION**

APR 11 1995

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

Approved by Menominee County  
 Land Survey Remonumentation  
 Peer Group Under Act 345 Of  
 P.A. Of 1990 On 12/9 199 94  
*William RLS*  
 ACTING Chairman

For corners in  
MENOMINEE  
 (County)

	Located In:	Corner Code #
1. Public Land Survey	T <u>33</u> N R <u>27</u> W	<u>L-09</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

RECEIVED FOR RECORD  
 94 DEC 12 AM 9:00  
 PAGE # 40 BK 4  
 BARBARA MORRISO  
 REGISTER OF DEEDS  
 MENOMINEE, MI 49825  
**Register of Deeds Stamp & File Number**

William Lenca Oct. 04 19 94  
 I, \_\_\_\_\_, in a field survey on \_\_\_\_\_, 19 \_\_\_\_\_, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

- A. Description of original monument and accessories and/or subsequent restoration:
- 1848: Original Survey by John Mullett - B.T.'s - Hemlock, 24" - N84°E - 05 lks; Birch, 8" - S17°W - 18 lks. All original evidence for this corner has been destroyed by farming activities.
  - 1979: Certified Survey No. 158 by George B. Wilson, RLS No. 17607, indicates that a concrete monument was established for the corner.

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
- We found a 4" square concrete monument in line with long standing fence and occupation lines running South and East - West from this location. The concrete monument is set in place of a large corner fence post. This location has been used for survey control by local surveyors for several years, and is accepted as the best available evidence of the position of the original corner.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- Set 3-1/4" dia. Alum. cap stamped for corner location on existing 4" square concrete monument:
- |                       |       |            |          |
|-----------------------|-------|------------|----------|
| 5" dia. White Ash     | N36°W | 15.61 feet | Scr. NBT |
| 12" dia. Yellow Birch | N72°E | 7.29 feet  | Scr. NBT |
| 10" dia. Yellow Birch | S12°E | 10.72 feet | Scr. NBT |
| 6" dia. White Ash     | S75°W | 22.11 feet | Scr. NBT |
| Survey Sign Post      | N90°E | 0.7 feet   |          |

NOTE: All bearings are magnetic bearings. All distances are measured with steel tape. Distances to trees are to nail in side of tree.

Signed by William Lenca Date Nov. 29, 1994  
 Surveyor's Michigan License No. 26461