

SURVEY & REMONUMENTATION

APR 11 1995

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

Approved by Menominee County
Land Survey Remonumentation
Peer Group Under Act 345 Of

P.A. Of 1990 On 12/9 199 94

For corners in **COMMISSION**

McLain RLS
ACTING Chairman
BARBARA MORRISON
REGISTER OF DEEDS
MENOMINEE, MI 49859
94 DEC 12 AM 9:01
RECEIVED FOR RECORD

<u>MENOMINEE</u> <small>(County)</small>	Located In:	Corner Code #:	
1. Public Land Survey	T <u>33N</u> R <u>27W</u>	<u>L-11</u>	
	T _____ R _____	_____	_____
	T _____ R _____	_____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____	_____
	S _____ T _____ R _____	_____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____	_____
	S _____ T _____ R _____	_____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	8	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

William Lenca in a field survey on Oct. 06 19 94

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1848: Original Survey by John Mullett - B.T.'s - Tamarack, 4" - N49°W - 03 lks; Tamarack, 5" - S30°W - 04 lks. No original evidence for this corner was recovered.
1988: L.C.R.C. No. 811 by William Lenca, RLS No. 26461, states that a 3/4" x 60" Alum. Rod/3" Alum. cap was set on line and midway between the NE and the NW Section Corners. B.T.'s: 8" W. Ash - N16°E - 33.95'; 6" W. Ash - S10°W - 4.16'; 10" W. Ash - N85°W - 19.66'; Carsonite Post - N68°E - 2.05'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

We recovered the 3/4" x 60" Aluminum Rod/3-1/4" dia. Aluminum cap and the 4 B.T.'s as noted in part "A". We found that this corner had been set erroneously. According to our field notes, we had intended to set the corner on line between the NE and the NW Section Corners of Section 36, T33N-R27W, and in line with an old North - South fence line rather than midway. We found that the corner had been set approximately 50 feet North of a straight line between corners. We therefore reset the corner on a straight line between section corners, and in line with the old North - South fence line.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Reset existing 3/4" x 60" Aluminum Rod/3-1/4" dia. Alum. cap stamped for corner:

10" dia. White Ash	N35°E	49.89 feet	Scr. NBT
12" dia. White Ash	S65°E	19.92 feet	Scr. NBT
8" dia. White Ash	S14°W	24.49 feet	Scr. NBT
9" dia. White Ash	N65°W	9.75 feet	Scr. NBT
Carsonite Marker Post	N50°E	1.7 feet	

NOTE: All bearings are magnetic bearings. All distances are measured with steel tape. Distances to trees are to nail in side of tree.

Signed by William Lenca Date Nov. 29, 1994
Surveyor's Michigan License No. 26461

141