

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

| | | |
|---------------------------------------|-------------|---------------|
| <u>MENOMINEE</u> (County) | Located In: | Corner Code # |
| 1. Public Land Survey | T33N R. 27W | M-3 |
| | T R | |
| | T R | |
| | T R | |
| 2. Property Controlling in Section | S T R | |
| | S T R | |
| 3. Miscellaneous Property in Sec. | S T R | |
| | S T R | |

95 DEC 27 PM 3:29
 RECEIVED FOR RECORD
 PAGE # 271 BK 4
 BARS/IRA/POST/SON
 REGISTERED DEEDS
 PERMITS 1995
 Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____
 (SAME AS CORNER A03 T33N-R26W)

| | | | | | | | | | | | | |
|----|---|----|---|----|---|----|---|----|---|----|---|----|
| | A | B | C | D | E | F | G | H | I | J | K | L |
| 1 | | | | | | | | | | | | |
| 2 | | 6 | | 5 | | 4 | | 3 | | 2 | | 1 |
| 3 | | | | | | | | | | | | |
| 4 | | 7 | | 8 | | 9 | | 10 | | 11 | | 12 |
| 5 | | | | | | | | | | | | |
| 6 | | 10 | | 17 | | 16 | | 15 | | 14 | | 13 |
| 7 | | | | | | | | | | | | |
| 8 | | 19 | | 20 | | 21 | | 22 | | 23 | | 24 |
| 9 | | | | | | | | | | | | |
| 10 | | 30 | | 29 | | 28 | | 27 | | 26 | | 25 |
| 11 | | | | | | | | | | | | |
| 12 | | 31 | | 32 | | 33 | | 34 | | 35 | | 36 |
| 13 | | | | | | | | | | | | |

I, William Lenca, in a field survey on Sep. 09, 1995, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1848: Original Survey by John H. Mullett - B.T.'s - Lynn, 14" - S30°W - 25 lks; Hemlock, 18" - N40°W - 06 lks. All original evidence has been destroyed by county road improvements.
- 1902: Record of Survey by Albert Haas, County Surveyor, shows partial subdivision of Section 12 and shows the location of corner M-3 as it relates to other corners in Section 12. Haas' record states that a 4" Cedar Post was set from Government B.T. (not recovered)
- 1981: L.C.R.C.No. 301 by William Lenca, RLS No. 26461, states that a Railroad Spike was set in accordance with existing lines of occupation. TIES: Tack in Power Pole - N30°W - 60.53' (found); Tack in Power Pole - S45°W - 44.12' (found); NW Corner of Garage - S47°E - 59.25' (found).

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

In our 1995 Remonumentation Survey, we recovered a Railroad spike in the centerline of County Roads running North - South and East - West matching the ties as described in L.C.R.C. No. 301 (see part "A"). We measured West from this location to the N1/4 Corner of Section 12, and found that our distance of 2502.04 feet matched closely with Albert Haas' 1902 record measurement of 2489.5 feet. We also measured South from this location to the E1/4 Corner of said Section 12, and found that our measurement of 2566.37 feet matched very closely with Albert Haas' 1902 record measurement of 2568.8 feet. This corner position has been used by local surveyors for approximately 90 years, and is accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 Set 5/8" x 24" Iron Rod/3-1/4" Alum. cap stamped for corner location in Monument Box:

| | | | |
|--|-------|------------|--------------|
| 5/8" x 24" Iron Rod/2" Alum. cap marked "WITNESS MARKER" | N61°E | 48.87 feet | @ Road Sign |
| 5/8" x 24" Iron Rod/2" Alum. cap marked "WITNESS MARKER" | S45°E | 49.82 feet | |
| 5/8" x 24" Iron Rod/2" Alum. cap marked "WITNESS MARKER" | S48°W | 39.52 feet | @ Power Pole |
| 5/8" x 24" Iron Rod/2" Alum. cap marked "WITNESS MARKER" | N28°W | 58.22 feet | @ Tel. Box |
| Survey Sign Post | S45°E | 50.5 feet | |

NOTE: All bearings are magnetic bearings. All distances are measured with a steel tape. Distances to trees are to nail in side of tree.

Signed by William Lenca Date Nov. 24, 1995
 Surveyor's Michigan License No. 26461

