

P.A. of 1990 On 12/20 19995

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Mr. David RLS
Chairman

For corners in

MENOMINEE
(County)

Located in: Corner Code #

- | | | |
|------------------------------------|-----------------------------|------------|
| 1. Public Land Survey | T <u>33</u> N R <u>27</u> W | <u>M-8</u> |
| | T___ R___ | _____ |
| | T___ R___ | _____ |
| | T___ R___ | _____ |
| 2. Property Controlling in Section | S___ T___ R___ | _____ |
| | S___ T___ R___ | _____ |
| 3. Miscellaneous Property in Sec. | S___ T___ R___ | _____ |
| | S___ T___ R___ | _____ |

RECEIVED FOR RECORD
95 DEC 27 PM 3:29
PAGE # 276
BARBARA WILSON
REGISTERED LAND SURVEYOR
MICHIGAN LICENSE NO. 26461

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____
(SAME AS A-8, T33N-R26W)

1	A	B	C	D	E	F	G	H	I	J	K	L
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	10		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

I, William Lenca, in a field survey on Mar 16, 1995 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1848: Original Survey by John H. Mullett - B.T.'s - S. Maple, 8" - S25°W - 20 lks; Hemlock, 16" - N40°W - 36 lks. All original evidence has been destroyed by county road improvements.
1979: Certified Survey No. 158 by George B. Wilson, RLS No. 17607, shows this corner as it relates to other corners in Section 24, T33N-R27W. The corner monument is described as an iron pin. No ties are given.
1983: Certified Survey No. 371 by George B. Wilson, RLS No. 17607, shows this corner as it relates to other corners in Sections 13 and 24, T33N-R27W. The corner monument is not described, and no ties are given.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

In our 1995 Remonumentation Survey in T33N-R27W, we recovered a 1/2 inch diameter iron rod in the centerline of county roads running North - South and East - West. Our measurements to corners 1 mile West and 1/2 mile North of this corner agree with George Wilson's measurements as recorded in Certified Survey No. 371. This corner has been accepted and used by local surveyors for at least 12 years, and is accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
Sct 5/8" x 24" Iron Rod/3-1/4" dia. Alum. cap stamped for corner location in Monument Box:

- | | | | |
|---|-------|-------------|--------------------|
| 7" dia. Jack Pine | N47°E | 51.29 feet | Scr. NBT |
| 7" dia. W. Pine | S43°E | 125.04 feet | Scr. NBT |
| 5/8" x 24" Iron Rod/2" dia. Alum. cap marked "WITNESS MARKER" | S58°W | 53.45 feet | |
| 5/8" x 24" Iron Rod/2" dia. Alum. cap marked "WITNESS MARKER" | N29°W | 87.66 feet | @ steel fence post |
| Metal Survey Sign Post | S58°W | 53.9' | |

NOTE: All bearings are magnetic bearings. All distances are measured with a steel tape. Distances to trees are to nail in side of tree.

Signed by William Lenca
Surveyor's Michigan License No. 26461

Date Dec. 11, 1995

