

SURVEY & REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

Approved by Menominee County
Land Survey Remonumentation
Peer Group Under Act 345 Of
P.A. of 1990 On 12/9 19994
McDermott RLS
ACTING Chairman

APR 1 1 1995

For corners in

MENOMINEE
(County)

COMMISSION

Located In:

Corner Code ##

- | | | |
|------------------------------------|---------------------------|-------------|
| 1. Public Land Survey | T <u>33N</u> R <u>27W</u> | <u>M-09</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

94 DEC 12 AM 9:0
RECEIVED FOR RECORD
PAGE # 142 BK. 1
BARBARA MORRISON
REGISTER OF DEEDS
MENOMINEE MI 49858
Register of Deeds Stamp & File Number

William Lenca

Sep. 19

94

I, _____, in a field survey on _____, 19 _____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therfore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

- 1847 - Original Survey (Township Exterior) by James H. Mullett - B.T.'s - Y. Birch, 14" - N34°W - 32 lks; Hemlock, 24" - S54°W - 15 lks. All original evidence for this corner has been destroyed by County Road improvements.
- 1848: Original Survey (Section Subdivisions) by John Mullett - B.T.'s - No new B.T.'s were recorded during section subdivisions.
- 1988: L.C.R.C. No. 811 by William Lenca, RLS No. 26461, states that a Railroad Spike was set in the centerline of a E-W (should be N - S) county road and in line with old fence south (should be west). Witnesses: Nail in Power Pole - West - 31.60'; Nail in 8" Poplar - Scr. B.T. - N40°W - 87.78'; Road Sign Post - S06°W - 149.00'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

We found the railroad spike and 3 witnesses as in proper location as noted in part "A". The corner falls in the centerline of a North - South County Road and in line with an old fence line running West from this location. This location fits well with old occupation lines to the North and South, and is accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 5/8" x 24" Iron Rod/3-1/4" dia. Alum. cap stamped for corner in Monument Box:

- | | | |
|---|-------|------------|
| 5/8" x 24" Iron Rod/2" dia. Alum. cap marked "WITNESS MARKER" | N42°E | 37.18 feet |
| 5/8" x 24" Iron Rod/2" dia. Alum. cap marked "WITNESS MARKER" | S34°E | 38.05 feet |
| 5/8" x 24" Iron Rod/2" dia. Alum. cap marked "WITNESS MARKER" | S43°W | 26.67 feet |
| 5/8" x 24" Iron Rod/2" dia. Alum. cap marked "WITNESS MARKER" | N40°W | 28.30 feet |
| Survey Sign Post | N90°W | 28.9 feet |

NOTE: All bearings are magnetic bearings. All distances are measured with steel tape.

Signed by William Lenca

Date Nov. 29, 1994

Surveyor's Michigan License No. 26461

142