

SURVEY & REMONUMENTATION

Approved by Menominee County
Land Survey Remonumentation
Peer Group Under Act 345 Of

P.A. of 1990 On 12/9 199 94

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in APR 1 1 1995

MENOMINEE
COMMISSION

Located In: _____ Corner Code # _____

- | | | | | | |
|------------------------------------|---|------------|---|------------|-------|
| 1. Public Land Survey | T | <u>33N</u> | R | <u>27W</u> | M-11 |
| | T | _____ | R | _____ | _____ |
| | T | _____ | R | _____ | _____ |
| | T | _____ | R | _____ | _____ |
| 2. Property Controlling in Section | S | _____ | T | _____ | R |
| | S | _____ | T | _____ | R |
| 3. Miscellaneous Property in Sec. | S | _____ | T | _____ | R |
| | S | _____ | T | _____ | R |

McDermis RLS
ACTING Chairman

RECEIVED FOR RECORD
94 DEC 12 AM 9:02
PAGE # 144 BK 4
BARBARA MORRISON
REGISTER OF DEEDS
MENOMINEE MI 49858

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	16		17		18		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

William Lenca

Oct. 06 19 94

I, _____, in a field survey on _____, 19 _____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1847: Original Survey (Township Exterior) by James H. Mullett - B.T.'s - Tamarack, 14" - N35°W - 29 lks; Tamarack, 12" - S20°W - 12 lks. All original evidence for this corner has been destroyed by County Road improvements.
1980: Certified Survey No. 178 by George B. Wilson, RLS No. 17607, indicates that a 4" square concrete monument 36" long was set in a cast iron monument box.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

We found a W-1-B Berntsen aluminum monument in the centerline of a North - South County Road in a location which fits with record measurements shown in Certified Survey No. 178. This corner is set proportionately between the E1/4 Corner of Section 25 and the SE Corner of Section 36, T33N - R27W. The corner has been used by local surveyors for 15 years, and is accepted as a careful and faithful re-establishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 5/8" x 24" Iron Rod/3-1/4" dia. Aluminum cap stamped for corner location in Monument Box:

12" dia. Tamarack	N33°E	93.21 feet	Scr. NBT
6" dia. White Ash	S83°E	34.86 feet	Scr. NBT
5" dia. Maple	S88°W	39.13 feet	Scr. NBT
12" dia. Tamarack	N31°W	83.29 feet	Scr. NBT
Survey Sign Post	West	31.0 feet	

NOTE: All bearings are magnetic bearings. All distances are measured with steel tape. Distances to trees are to nail in side of tree.

Signed by William Lenca

Date Dec. 05, 1994

Surveyor's Michigan License No. 26461

144