

SURVEY & REMONUMENTATION

APR 1 1 1995

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Approved by Menominee County
Land Survey Remonumentation
Peer Group Under Act 345 Of
P.A. Of 1990 On 12/9 19994
McLain RLS
ACTING Chairman

For corners in **COMMISSION**

<u>MENOMINEE</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>33N</u> R <u>27W</u>	<u>M-12</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

RECEIVED FOR RECORD
94 DEC 12 AM 9:02
PAGE # 145 BK 4
BARBARA MORRISON
REGISTER OF DEEDS
MENOMINEE, MI 49858
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

William Lenca in a field survey on Oct. 31, 1994

I, _____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
- 1847: Original Survey (Township Exterior) by James H. Mullett - B.T.'s - Hemlock, 12" - N10°W - 10 lks; Y. Birch, 8" - S70°W - 07 lks. All original evidence for this corner has been destroyed by County Road improvements.
 - 1887: F.J. Merrian, Deputy Surveyor, surveyed Section 36. His record indicates the distances 1/2 mile North and 1/2 mile South to be 40.935 chains or 2701.71 feet.
 - 1980: Certified Survey No. 178 by George B. Wilson, RLS No. 17607, shows a subdivision of Section 31, T33N-R26W, indicating the position of this corner as midway and on line between section corners. No corner monument is shown or described.

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
- We found a P.K. nail 6 feet West of the centerline of a North - South county road and set midway and on line between the NE Corner and the SE Corner of Section 36, T33N-R27W. This position fits the record measurements shown in Certified Survey No. 178. Wilson's distance for 1/2 mile to the North and 1/2 mile to the south of this corner is 2706.4 feet. This matches closely with F.J. Merrian's measurement of 2701.71 feet for these same distances. We accepted this corner location as a careful and faithful re-establishment of the position of the original corner.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- Set 5/8" x 24" Iron Rod/3-1/4" dia. Aluminum cap stamped for corner location in Monument Box:
- | | | | |
|------------------|-------|------------|----------|
| 9" dia. Cedar | N42°E | 96.93 feet | Scr. NBT |
| 8" dia. Cedar | S50°E | 59.46 feet | Scr. NBT |
| 8" dia. Cedar | S51°W | 51.04 feet | Scr. NBT |
| 8" dia. Cedar | N24°W | 55.24 feet | Scr. NBT |
| Survey Sign Post | East | 37.6 feet | |

NOTE: All bearings are magnetic bearings. All distances are measured with steel tape. Distances to trees are to nail in side of tree.

Signed by William Lenca Date Dec. 05, 1994
Surveyor's Michigan License No. 26461

145