

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
MENOMINEE
 (County)

Located In: Corner Code #

1. Public Land Survey T33N R 28W K-9
 T R
 T R
 T R

2. Property Controlling S T R
 in Section S T R

3. Miscellaneous S T R
 Property in Sec. S T R

RECORDED FOR RECORD
 97 JUL 23 PM 3:34
 PAGE # 484 BK 5
 BARBARA MORRISON
 REGISTER OF DEEDS
 MENOMINEE MI 49863
 Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, William Lenca, in a field survey on July 07, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1848: Original Survey by John Mullett - B.T.'s - W. Pine, 30" - S77°E - 38 lks.; Birch, 10" - N72°W - 23 lks. All original evidence for this corner has been destroyed by county road improvements.
- 1981: CERTIFIED SURVEY No. 217 recorded by George B. Wilson, RLS No. 17607, shows a section breakdown for fractional Section 26, T33N-R28W. This corner is shown with ties to other corners. A corner monument is indicated but not described and no witnesses are given.
- 1995: CERTIFIED SURVEY No. 855 recorded by William Lenca, RLS No. 26461, shows a tie to this corner and describes it as an existing railroad spike. Witnesses: 5/8" x 24" Iron Rod/Ident. cap - North - 33.03'; 5/8" x 24" Iron Rod/2" Alum. cap 0.5' E of Rd. Sign - S32°E - 44.00'; 5/8" x 24" Iron Rod/2" Alum. cap 1' NE of Power Pole - S38°W - 39.44'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

We found a railroad spike in the centerline of county roads running East - West and South, and in line with an old cemetery fence to the north. The existing railroad spike fits measurements as recorded in Certified Survey No. 217 and No. 855, and is accepted as the best available evidence of the position of the original corner.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 5/8" x 24" Iron Rod/3-1/4" dia. Alum. cap stamped for corner location in Monument Box:

5/8" x 24" Iron Rod/Ident cap (MI 26461/WI 1569)	North	33.03 feet	
5/8" x 24" Iron Rod/2" dia. Alum. cap marked "WITNESS MARKER"	S32°E	44.00 feet	0.5' E of Road Sign
5/8" x 24" Iron Rod/2" dia. Alum. cap marked "WITNESS MARKER"	S38°W	39.44 feet	1' NE of Power Pole
Metal Survey Sign Post	S32°E	44.8 feet	
Nothing else nearby			

NOTE: All bearings are magnetic bearings. All distances are measured with steel tape. Distances to trees are to nail in side of tree.

Signed by William Lenca Date July 14, 1997
 Surveyor's Michigan License No. 26461

REMONUMENTATION
 DEC 22 1997
 COMMISSION