

LAND CORNER RECORDATION CERTIFICATE  
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in  
MENOMINEE  
 (County)

Located In: Corner Code #

1. Public Land Survey T33N R 28W K-10  
 T R  
 T R  
 T R

2. Property Controlling S T R  
 in Section S T R

3. Miscellaneous S T R  
 Property in Sec. S T R

97 JUL 23 PM 3:34  
 REGISTERED FOR RECORD  
 PAGE # 485/485  
 BARBARA MORRISON  
 REGISTER OF DEEDS  
 MENOMINEE, MICHIGAN  
 Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, William Lenca, in a field survey on July 07, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

- 1848: Original Survey by John Mullett - B.T.'s - Hemlock, 9" - N64°E - 25 lks.; Birch, 6" - S71°W - 18 lks. All original evidence for this corner has been destroyed by county road improvements.
- 1981: CERTIFIED SURVEY No. 217 recorded by George B. Wilson, RLS No. 17607, shows a section breakdown for fractional Section 26, T33N-R28W. This corner is shown with ties to other corners. A corner monument is indicated but not described and no witnesses are given.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

We recovered a railroad spike 6 inches below the centerline of a gravel surface county road, and in line with an ancient fence line running East. The position of the railroad spike matches measurements shown in Certified Survey No. 217, and is accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Set 2" dia. Aluminum Pipe 30" long/3-1/4" dia. Alum cap stamped for corner location:
- 9" dia. Oak N35°E 40.14 feet Scr. NBT
- 12" dia. Norway Pine S63°W 37.89 feet Scr. NBT
- 11" dia. Maple N14°W 76.79 feet Scr. NBT
- 5/8" x 24" Iron Rod/plastic ID cap East 33.01 feet
- Metal Survey Sign Post East 34.0 feet

NOTE: All bearings are magnetic bearings. All distances are measured with steel tape. Distances to trees are to nail in side of tree.

Signed by William Lenca Date July 14, 1997  
 Surveyor's Michigan License No. 26461



REMONUMENTATION

DEC 22 1997  
 COMMISSION

485