

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

Alvin R. S.
 Chairman

For corners in

MENOMINEE (County)	Located In:	Corner Code #
1. Public Land Survey	T33N R 28W	L-11
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

REGISTERED FOR FILING
 1997 JUL 23 PM 3:34
 PAGE # 488 OKS
 BARBARA MORRIS, CN
 REGISTER OF DEEDS
 MENOMINEE, MI 49858
 Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, William Lenca, in a field survey on July 09, 1997, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	13		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

- 1848: Original Survey by John Mullett - B.T.'s - B. Ash, 6" - N13°W - 15 lks.; B. Ash, 4" - S41°E - 06 lks. All original evidence for this corner has been destroyed by county road improvements.
- 1901: Survey by Albert Hass, Menominee County Surveyor, states "sect 4" Cedar post from Government B.T." (Destroyed by County Road Improvements.)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

We found a Railroad Spike in the centerline of County Roads running East - West and South, and in line with an old fence running North. This position fits closely with the 1901 Albert Hass Survey and is accepted as the best available evidence of the position of the original corner.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set	Monument	Bearing	Distance	Notes
5/8" x 24" Iron Rod	3-1/4" dia. Alum. cap stamped for corner location in Monument Box	N54°E	40.47 feet	Scr. NBT
4" dia. White Ash		S35°E	36.92 feet	1' W. of Power Pole
5/8" x 24" Iron Rod	2" dia. Alum. cap marked "WITNESS MARKER"	S48°W	34.71 feet	0.9' E of Road Sign
5/8" x 24" Iron Rod	2" dia. Alum. cap marked "WITNESS MARKER"	N16°W	33.30 feet	Scr. NBT
7" dia. White Ash		S35°E	37.4 feet	
Metal Survey Sign Post				

NOTE: All bearings are magnetic bearings. All distances are measured with steel tape. Distances to trees are to nail in side of tree.

Signed by William Lenca Date July 18, 1997
 Surveyor's Michigan License No. 26461

REMONUMENTATION

DEC 22 1997

COMMISSION