

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Approved by Menominee County
Land Survey Remonumentation
Peer Group Under Act 345 Of
P.A. of 1990 On 12/12, 1996
Mr. David RLS
Chairman

For corners in

<u>MENOMINEE</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>33N</u> R <u>27W</u>	<u>A04</u>
	T <u>33N</u> R <u>28W</u>	<u>M-4</u>
2. Property Controlling in Section	S <u> </u> T <u> </u> R <u> </u>	
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	

REGISTER OF DEEDS
BARBARA J. MORRISON
REGISTER OF DEEDS
TERRACE, MICHIGAN 49801

96 DEC 20 AM 9:30
PAGE # 409, BK 4

RECEIVED FOR RECORD

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

SAME AS CORNER M-04 T33N-R28W ✓

I, William Lenca, in a field survey on Apr 24, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4	7		8		9		10		11		12		
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

- 1847: Original Survey (Twp Bdy) by James H. Mullett - B.T.'s - Y. Pine, 30" - S57°W - 49 lks; Beech, 8" - N47°W - 21 lks. All original evidence for this corner has been destroyed by clearing & farming activities.
- 1974: L.C.R.C. No. 72, Book 1 recorded by George B. Wilson, RLS No. 17607, states "No original evidence found - Re set by single proportion north and south. Measurement to E1/4 Corner. Corner Monument - 2" dia. x 30" long pipe filled with concrete, stamped brass cap, anchor at bottom." BT's - 165° azm. - 2" Maple - 114.4'; 157° azm. - 3" Oak - 107.6'; 142° azm. - 3" Maple - 131.6'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

We found a 2 inch diameter iron pipe with a 2-1/4 inch diameter brass cap at a single proportional position between the NW Corner and the SW Corner of Section 7, and in line with the centerline of an old lane running South and a field occupation to the North. We also found 3 B.T.'s as described in L.C.R.C. No. 72. (See part "A"). This corner has been accepted and used by local surveyors for at least 22 years, and is accepted as a careful and faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Accepted existing 2" dia. Iron Pipe/2-1/4" dia. Brass cap stamped for corner location:

10" dia. Hemlock	S77°E	29.00 feet	Scr. NBT
10" dia. White Oak	S18°E	108.03 feet	Scr. NBT
14" dia. Hemlock	S38°W	136.13 feet	Scr. NBT
Metal Survey Sign Post	N88°W	33.4 feet	



NOTE: All bearings are magnetic bearings. All distances are measured with steel tape. Distances to trees are to nail in side of tree.

Signed by William Lenca
Surveyor's Michigan License No. 26461

Date Nov. 18, 1996