

3

Approved by Menominee County  
Land Survey Reomonumentation  
Per Group Under Act 345 Of  
P.A. Of 1990 On 10/31/97 1892  
Alfred L. Lenca PLS 1  
Chairman

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in  
**MENOMINEE**  
(County)

Located In: Corner Code #

1. Public Land Survey

T2N R28W  
T32N-R27W  
T33N R27W  
T32N R28W

M-1  
A-13  
M-13

2. Property Controlling  
in Section  
3. Miscellaneous  
Property in Sec.

S T R  
S T R  
S T R  
S T R

4. Lot No. Recorded Plat

5. Private Claims  
SAME AS CORNERS M-13, T33N-R28W; A-13, T33N-R27W; M-1, T32N-R27W

I, William Lenca, in a field survey on Mar. 24, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Register of Deeds Stamp & File Number

	B	C	D	E	F	G	H	I	J	K	L	M
1												
2												
3												
4												
5												
6												
7												
8												
9												
10												
11												
12												
13												

A. Description of original monument and accessories and/or subsequent restoration:  
1847: Original Survey by John Mulcahy - B.T.'s - Cedar, 10" - N48°E - 33 lbs.; Cedar, 10" - N60°W - 30 lbs. No original evidence for this corner was recovered.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
This corner was re-established by double proportional measurement between the NE Corner (K-1) of Section 2, T32N-R28W and the N1/4 Corner (B-1) of Section 6, T32N-R27W for East - West position, and between the E1/4 Corner (M-12) of Section 36, T33N-R28W and the W1/4 Corner (A-4) of Section 7, T32N-R27W for North - South position, and is accepted as a careful and faithful reestablishment of the position of the original corner. The corner falls in a tamarack and spruce swamp - there is no occupational evidence in this area.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
Set 2" dia. Aluminum Pipe/3-1/4" dia. Alum cap staked for corner location:

6" dia. Cedar	N56°E	22.99 feet
7" dia. Tamarack	S20°E	8.58 feet
10" dia. Tamarack	N68°W	27.74 feet
7" dia. Tamarack	N02°E	24.11 feet
Metal Survey Sign Post	North	1.0 feet

Ser. NDT  
Ser. NBT  
Ser. NBT  
Ser. NBT

NOTE: All bearings are magnetic bearings. All distances are measured with steel tape. Distances to trees are to nail in side of tree.

Date Apr. 08, 1997

Signed by Alfred L. Lenca  
Surveyor's Michigan License No. 20401

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 26, 1977  
REVISED MAY 14, 1987  
REVISED JUN. 1988  
REVISED OCT. 1990



542