

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD


Menominee COUNTY
35
T 34 N R 25 W

DESCRIPTION OF CORNER Section corner for sections 33/34 T35N R25W
4/3 T34N R25W

CORNER MONUMENT 1" iron pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED 4/23/70, F. J. Bray

WITNESSES TO CORNER..... 3/4" iron pipe S 83° W, 6.88'



9" Hemlock (NBT) N 03° W, 29.4'

18" W. Pine (NBT) S 08° E, 32.7'

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was placed at the point a 1½" x 3/8" iron which had been witnessed by the Michigan State Highway Department in 1948. This iron is now missing. Using the witness trees the point where the iron had been could be seen. Also points of two rotted stakes were found.

SURVEYOR'S SEAL

DISTRIBUTION:

SIGNED Frank J. Bray DATE 6/28/70
REGISTERED LAND SURVEYOR
Frank J. Bray

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68