

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 34 NR. 25 W.

Menominee COUNTY

DESCRIPTION OF CORNER Section Corner common to Sec. 19-20-29-30

DESCRIPTION OF CORNER MONUMENT 1 1/2" iron pipe

WITNESSES TO CORNER 14" W. Pine S 56° Wc 249 links
Marked "NBT"

6" W. Ash N 61° W 115 1/2 links
Marked "NBT"

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Re-witnessed Section Corner as set by unknown surveyor.

Section Corner lies in line with County Road to west and on beach.

Corner lies 2.25 chs. east of approx. $\frac{1}{2}$ of old highway M-35.

NOTE: This Section Corner is also intended as a meander corner according to original Gov't Field Notes.

Corner found by Forestry Division Survey Crew while making a partial re-tracement survey in this area.

SURVEYORS SEAL

SIGNED Billy D. Buckles DATE 3/26/57
REGISTERED LAND SURVEYOR