

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES
LAND CORNER RECORD


Menominee COUNTY
35
T 34 N R 25 W

DESCRIPTION OF CORNER Section corner for sections 32/33 T35NR25W
5/4 T34NR25W

CORNER MONUMENT 1" iron pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED 5/4/70, F. J. Bray

WITNESSES TO CORNER..... 6" Cedar (S.4) (NBT) S 67° E, 14.9'



8" Cedar (S.5) (NBT) S 01° W, 23.8'

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was reestablished by double proportioned measurement between 1/4 corners 1 1/2 miles north and to west and 1/2 mile to east and section corner one mile to south. No original evidence found. Wood post marked approximate corner near.

SURVEYOR'S SEAL

DISTRIBUTION:

SIGNED

Frank J. Bray
REGISTERED LAND SURVEYOR

DATE

6/25/70

Frank J. Bray

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68