

STATE OF MICHIGAN  
DEPARTMENT  
OF  
NATURAL RESOURCES  
LAND CORNER RECORD


Menominee COUNTY  
T 35  
34 N R's 25 & 26 W

DESCRIPTION OF CORNER Town corner for sections T34N R26W 36/31 T35N R25W  
1/6 T34N R25W

CORNER MONUMENT 1" iron pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED 4/15/70, F. J. Bray

WITNESSES TO CORNER..... 8" Cedar (S.36) (NBT) N 03° W, 56.0'



7" Cedar (S.31) (NBT) N 66° E, 43.3'

12" Tamarack stub (NBT) S 02° E, 13.9'

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was replaced from two wood posts. Found rotted tamarack stump bottoms in proper bearings and distances from posts. These rotted stump bottoms could be possible original B.T.'s. Ridge to the north checks well with original notes.

SURVEYOR'S SEAL

DISTRIBUTION:

SIGNED

Frank J. Bray  
REGISTERED LAND SURVEYOR  
Frank J. Bray

DATE

6/25/70

County Courthouse  
Area Forester (Regions I & II)  
District or Region Surveyor  
Forestry Div., Lansing

R 4047  
Rev. 10/68