

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

MENOMINEE

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY_____	T. 34 N. S., R. 25 E. W.	C-2
2. PROPERTY CONTROLL- 6 ING IN SECTION_____	T. 34 N. S., R. 25 E. W.	7
3. MISCELLANEOUS PROPERTY IN SECTION_____	T. _____ N. S., R. _____ E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND
FILING NUMBER

I, David B. Babbitt, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 8/10, 19 82, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- C-2 East 1/4 corner of Section 6; wood post - Birch 6 - N48° E - 10 lks; Aspen 10 - S22°W - 13 lks.
7 N 1/16 corner on the East section line of Section 6; not previously established.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- C-2 Set on line between the N.E. & S.E. section corners of Section 6 with measurements proportioned to the G.L.O. record.
7 Set on line between the N.E. section corner and the E. 1/4 corner of Section 6 with measurements proportioned to the G.L.O. record.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- C-2 1" pipe, 4" aluminum cap; 6" R. Maple S16°W 29.6'; 10" W. Birch N53°W 14.3'; 16" R. Maple S54°E 28.0'; 5" R. Maple N63°E 46.2'.
7 1" pipe, 4" aluminum cap; 9" W. Birch N78°W 12.6'; 5" Balsam Fir N4°W 26.8'; 4" B. Ash S89°E 24.2'; 6" B. Ash S18°E 36.1'.

SIGNED BY

David B. Babbitt

DATE

8-12-82

SURVEYOR'S MICHIGAN REGISTRATION NO. 21558

(SEAL)

FOR STATE AND UNITED STATES AGENCIES: