

# LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF --:	LOCATED IN --:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 34N N. S., R. 25W E. W.	D-3 & C-3
2. PROPERTY CONTROLLING IN SECTION	T. _____ N. S., R. _____ E. W.	
3. MISCELLANEOUS PROPERTY IN SECTION	T. _____ N. S., R. _____ E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, David B. Babbitt, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on January 26, 1983, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- D-3 - North 1/4 Cor. of Sec. 8; Curtis Anderson - local resident states that during W.W.II he helped a surveyor named Jenkins of Menominee to do some survey work in the area. During the course of said survey surveyor Jenkins found some pieces of limestone which he said had been placed previously to mark the North 1/4 Cor. of Sec. 8. No N.B.Ts were mentioned, but he did say they were in a N-S fence line about 6' to 10' South of a fence corner.
- C-3 - S.E. Sec. Cor. of Sec. 6; wood post - Tam. 12" - N57°E 20 Lks; Tam. 8" - S44°E - 11 Lks

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- D-3 - Found pieces of limestone in old N-S fence 6½' South of a fence corner, as described to me by Curtis Anderson, local resident. (See part "A" above).
- C-3 - Set D.N.R. Mon. in line with center line of roads South & West and in line with old fence East. Swamp and marsh calls from the G.L.O. notes fit, North for 1/2 mile and East for 3.60 Chs. (No other calls for 70 Chs.) However the Mea. East to an existing Sec. Cor. is over 7 chains longer than record. Mea. in the other 3 directions are slightly long also. O.B.T.s were probably destroyed by road construction.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- D-3 - D.N.R. Mon.; 4" Red Maple - S46°E - 28.9'; 5" R. Maple - N85°E - 26.6'; 10" Balsam - N58°E - 20.3'; 6" R. Maple - N27°W - 54.6'.
- C-3 - D.N.R. Mon.; 6" Poplar - N65°W - 30.8'; 5" Cedar - N12°E - 31.6'; 8" Ash - S29°E - 29.5'; 6" Poplar - S55°W - 5.3'.

SIGNED BY

*David B. Babbitt*

DATE

2-14-83

SURVEYOR'S MICHIGAN REGISTRATION NO.

21558

(SEAL)