

LAND CORNER RECORDATION CERTIFICATE

MENOMINEE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY.....	T. 34 N. S., R. 25 W.	C-2, C-4, D-4
2. PROPERTY CONTROLLING IN SECTION.....	T. N. S., R. E. W.	
3. MISCELLANEOUS PROPERTY IN SECTION.....	T. N. S., R. E. W.	
4. LOT NO., RECORDED PLAT		
5. PRIVATE CLAIMS		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, David B. Babbitt, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on May 4, 1983, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- C-2 - East 1/4 Cor. of Sec. 6.
- C-4 - W 1/4 of Sec. 8; original BT's - Cedar 14" - S19°E - 18 links; Cedar 14" - S24°W - 21 links.
- D-4 - Center 1/4 Cor. of Sec. 8.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- C-2 - Two of the recorded N.B.T.s taken on 8-2-82 were destroyed by re-routing woods road. Took these two new B.T.s to replace those destroyed.
- C-4 - Set on line between the N.W. & S.W. Sec. Cors. of Sec. 8 and in line with center line of road East & old fence line West. Cor. falls 1.5' West of center line of N-S blacktop road.
- D-4 - Set at the intersection of the N-S and E-W 1/4 lines of Sec. 8.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- C-2 - D.N.R. Monument; 15" R. Maple - S81°E - 37.9'; 9" W. Birch - S41°W - 21.8'.
- C-4 - Menominee County Monument; 7" Ash - N45°W - 77.1'; 8" Ash - S63°W - 57.5'; 4" Ash - S50°E - 67.7'; Stop Sign - N59°E - 43.1'.
- D-4 - D.N.R. Monument; 5" Cedar - S57°E - 62.9'; 10" R. Maple - S11°W - 51.6'; 5" (Twin) Ash - N24°W - 37.5'; 4" Oak - N50°E - 45.3'.

SIGNED BY

David B. Babbitt

DATE

9-15-83

SURVEYOR'S MICHIGAN REGISTRATION NO. 21558

(SEAL)