

1992 RECEIVED FOR RECORD APR 28 AM 11:11

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

PAGE # 935 Bk 3 HENRY GUROSH REGISTER OF DEEDS MEMPHINEE, MI 49858

For corners in Menominee (County) Located In: Corner Code # 1. Public Land Survey 2. Property Controlling in Section S 30 T 34N R 25W 3. Miscellaneous Property in Sec. 4. Lot No. 5. Private Claims

Register of Deeds Stamp & File Number

I, Paul R. Bressette, in a field survey on 12-19-91 & 4-5, 19 92, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

Grid table with columns A-M and rows 2-13. Cell (10, A) contains a dot and the number 30.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration: 3. North One-sixteenth corner common to Sections 25 and 30. Not set in original survey, no evidence of subsequent establishment. 4. Northwest One-sixteenth corner of Section 30. Not set in original survey, no evidence of subsequent establishment. 8. West One-sixteenth corner of Section 30. Not set in original survey, no evidence of subsequent establishment.

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner: 3. Corner established mid-point and on-line between the Northwest and West Quarter corners of Section 30. 4. Corner established at the intersection of the North and West One-sixteenth lines of Section 30. Section 30 was originally surveyed as a regular section with no fractional forties on the west side. 8. Corner established mid-point and on-line between the West Quarter and Center Quarter corners of Section 30. Section 30 was originally surveyed as a regular section with no fractional forties on the west side.



- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner: 3. 1" pipe with 4" aluminum cap 5" B. Ash (1/16S,BT) N 82° E 6.2'; 7" Cedar (1/16S,BT) S 18° E 18.9'; 5" Cedar (1/16S,BT) S 50° W 11.5'; 4" Cedar (1/16S,BT) N 60° W 13.6'. 4. 1" pipe with 4" aluminum cap 8" B. Spruce (1/16S,BT) N 29° E 13.8'; 12" Cedar (1/16S,BT) S 03° W 13.8'; 7" Cedar (1/16S,BT) S 45° W 15.6'; 4" Cedar (1/16S,BT) N 01° W 20.35'. 8. 5/8" rebar with plastic cap 6" Cedar (1/16S,BT) N 56° E 72.4'; 6" Tamarack (1/16S,BT) S 54° E 117.85'; 5" Tamarack (1/16S,BT) S 18° W 73.15'; 11" Cedar (1/16S,BT) N 27° W 61.4'. Corner lies north of the north edge of pavement of CO. RD. 338.

Signed by Paul R. Bressette Date 4-28-92 Surveyor's Michigan License No. 37270

99 935 ✓