

APR 06 1999

Approved by Menominee County
Land Survey Remonumentation
Peer Group Under Act 345 Of
P.A. Of 1999 On 12/30 1999
William Lenca
Chairman

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in SECTION

MENOMINEE (County)	Located In:	Corner Code #
1. Public Land Survey	T34N R 25W	B-07
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

RECEIVED FOR RECORD
99 JAN -6 AM 9:56
PAGE # 743 BLS
BARBARA MORRISON
REGISTER OF DEEDS
MENOMINEE, MI 49859
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, William Lenca, in a field survey on Dec. 15, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7	●												
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

1848: Original Survey by John Mullett - B.T.'s - Cedar, 12" - N46°W - 13 lks.; Fir, 4" - S45.5°W - 16 lks. All original evidence for this corner has been destroyed by logging and road improvements.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

We set this corner in the centerline of an old lane running East - West and in line with an ancient fence line running South from this position. This location fits with a 2 inch diameter Iron Pipe found at the W1/16 corner on the south line of Section 18, T34N - R25W. This location also fits within 3 feet of a GLO terrain call to a stream 478.5' West, and matches closely with a single proportional location, and is accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 2" dia. Aluminum Pipe 30" long/3-1/4" dia. Alum. cap stamped for corner location:

8" dia. White Ash	N42°E	37.08 feet	"X" cut in upper & lower blazes
16" dia. Cedar	S42°E	42.53 feet	"X" cut in upper & lower blazes
22" dia. Cedar	S17°W	20.64 feet	"X" cut in upper & lower blazes
6" dia. Cedar	N37°W	36.53 feet	"X" cut in upper & lower blazes
Metal Survey Sign Post	South	20.8 feet	

NOTE: All bearings are magnetic bearings. All distances are measured with steel tape. Distances to trees are to nail in side of tree.

Signed by William Lenca
Surveyor's Michigan License No. 26461

Date Dec. 23, 1998

