MICHIGAN DEPARTMENT OF CONSERVATION FORESTRY DIVISION

LAND CORNER RECORD

T. 34 N.R. 26 W

		Menominee	COUNTY
DESCRIPTION OF CORNER	Section corner for sections	22/23 27/26	
CORNER MONUMENT	1" iron pipe with 4" aluminum cap		
DATE MONUMENT PLACED AND	WITHESSED <u>5/3/68, F. J. Bre</u>	ay	
VITNESSES TO CORNER	. 4" B. Spruce (S.22)(NBT) N	05° W. 10½ links	
2 6	5" B. Spruce (S. 26)(NBT) S		
CIRCLE CORNER REGISTERED	AND		

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was reestablished by double proportioned measurement to section corner 2 miles East. 1/4 corner 1/2 mile north. South to £ of road intended to be on E-W $\frac{1}{4}$ line & £ of road. 1 mile west intended to be on section line.

SURVEYOR'S SEAL

SIGNED Frank J. Bray DATE 5/24/68