

6123

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Menominee</u> <small>(County)</small>	Located In:	Corner Code <u>##</u>
1. Public Land Survey	T <u>34N</u> R <u>26W</u>	<u>K-6, M-6</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, David B. Babbitt, in a field survey on 6/3, 19 86, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

K-6. West 1/4 corner of Section 13. 1" pipe with 4" brass cap-set 5/8/56.
9" cedar - S41N, 86 Lks.
7" hemlock - N22W, 24 Lks.

M-6. East 1/4 corner of Section 13.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-6. Could not find monument. Set new DNR monument from 1956 NBTs and marked two additional NBTs.

M-6. Found square cedar post with remains of older square post beside it. Could not find any evidence of the original Gov't. survey but this post is near MPOL between the NE and SE section corners and I see no reason to question it. Set monument beside post.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-6. DNR Monument. 6" cedar S70W, 20.0'
10" cedar N19E, 57.2'

M-6. DNR Monument. 4" cedar N2E, 13.6'
4" cedar N72E, 10.15'
4" cedar S73E, 13.7'
3" cedar, S43E, 14.45'

Signed by David B. Babbitt

Date 9-10-86

Surveyor's Michigan License No. 21558