

01/8

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

Menominee (County) Located In: \_\_\_\_\_ Corner Code ##

1. Public Land Survey T 34N R 26W L-5, K-7, M-5  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_

2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

Register of Deeds Stamp & File Number

I, David B. Babbitt, in a field survey on 5/22, 1986, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

- L-5. North 1/4 cor. of Section 13. Wood post. Cedar 18 - S35W, 25 Lks.  
DO 15 - N55E, 23 Lks.
- K-7. Southwest section corner of Section 13. 1" pipe with 4" aluminum cap. Set 5-12-68.  
8" aspen S67E, 26 1/2 Lks.  
6" w. pine S12W, 46 Lks.  
7" w. birch N23W, 51 Lks.
- M-5. Northeast section corner of Section 13. 1" pipe with brass cap set 1-9-59.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- L-5. Set M.P.O.L. between the NE and NW section corners of Section 13. Could not identify either OBT.
- K-7. Found DNR Monument in place. Rewitnessed as found.
- M-5. Found Conservation Department brass capped monument. NW NBT in place in good condition. Marked new BTs.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- |                           |                        |                                       |
|---------------------------|------------------------|---------------------------------------|
| L-5. DNR Monument.        | K-7. DNR Monument.     | M-5. 1" pipe with 4" brass cap.       |
| 10" cedar N25W, 102.6'    | 12" w.pine S9W, 29.7'  | 5" w. spruce S77E, 12.4'              |
| 8" cedar N67E, 66.0'      | 4" cedar N26E, 55.8'   | 6" r.maple S49W, 12.0'                |
| 6" hard maple S33E, 36.1' | 9" w.ash N16W, 29.0'   | 5" balsam N21E, 2.5'                  |
| 3" hemlock S70W, 22.0'    | 5" w.birch S51E, 43.4' | 1959 NBT, 6" soft maple N71W, 35 Lks. |

Signed by David B. Babbitt Date 9-10-86  
 Surveyor's Michigan License No. RLS 21558