

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Menominee</u> <small>(County)</small>	Located In:	Corner Code <u>##</u>
1. Public Land Survey	T 34N R 26W	I-7, J-7
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, David Babbitt, in a field survey on 7/22/86, 19____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- I-7. Southwest section corner of Section 14. Wood post. Hemlock 14, N10E, 12 Lks.
Do 22, S46E, 19 Lks.
- J-7. South 1/4 corner of Section 14. Wood post. Cedar 20 - N67E, 04 Lks.
B.ash 12 - S85W, 10 Lks.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- I-7. Set DNR monument in line with ζ of road east and in line with brushed out line north which Emil Lubka, long time (70 years) local resident, says is the same line where a fence (decayed and fallen down 50 years ago) was located. This point falls nearly in line with the ζ of a road south also. A Mr. Brendemihl, another long time resident, states that there was a pipe in the road intersection approx. 20 years ago. I could not find said pipe.
- J-7. Set DNR monument in ζ of E-W county road and in line with ζ of old road grade north which Emil Lubka, long time (70 years) resident, says was a twp. road built on the 1/4 line of Section 14. Measurements east and west fit well to established section corners.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- I-7. DNR Monument. Nail & brass tag in the side. { Power pole S50°W, 49.1'
8" elm S78°E, 55.65'
28" h.maple N36°E, 26.7'
- SE cor. of house, N25W, 35.9'
- J-7. DNR monument. 7" tamarack N70°W, 53.3'
8" tamarack N29°W, 32.8'
9" tamarack N67°E, 65.1'
5" tamarack S34°E, 36.4'

Signed by David B. Babbitt Date 9-11-86

Surveyor's Michigan License No. 21558