

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

<u>Menominee</u> <small>(County)</small>	Located In:	Corner Code <i>##</i>
1. Public Land Survey	T <u>34N.</u> R <u>26W</u>	<u>I-6.</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S <u>15</u> T <u>34N.</u> R <u>26W</u>	<u>8, 3.</u>
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, David Babbitt, in a field survey on 10/8, 19 86  
do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned  
in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the  
current manual of survey instructions of the United States Department of the Interior, Bureau of Land  
Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5  
above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a  
Court of Law; established, re-established, monumented, re-monumented, recovered, found as  
expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded  
on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

- I-6. W 1/4 corner of Section 14. Set 1/4 section post in TAM 10".  
Tam. 8, N20E, 10 Lks.
- 8. W 1/16 corner on the E-W 1/4 line of Section 14. Not prev. established.
- 3. N 1/16 on west section line of Section 14. Not prev. established.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- I-6. Set MPOL between the SW and NW section corners of Section 14. Several dead and down  
tamarack in the area but could not find marks on any.
- 8. Set MPOL between the West 1/4 corner and the center of Section 14.
- 3. Set MPOL between the West 1/4 corner and the NW section corner of Section 14.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- |                          |                           |                            |
|--------------------------|---------------------------|----------------------------|
| I-6. DNR Monument.       | 8. DNR Monument.          | 3. DNR Monument.           |
| 8" tamarack, S47E, 8.3'  | 5" b.spruce, S60W, 12.50' | 9" sugar maple, S15W, 3.2' |
| 4" tamarack, N42E, 12.5' | 7" cedar, N37W, 7.85'     | 6" hemlock, S81W, 43.35'   |
| 5" cedar, N40W, 15.35'   | 3" cedar, N45E, 25.55'    | 5" sugar maple, N7W, 5.2'  |
| 10" cedar, S31W, 19.00'  | 5" tamarack, S31E, 4.73'  | 5" hemlock, N78E, 50.2'    |

Signed by David B. Babbitt Date 1-27-87  
 Surveyor's Michigan License No. RLS 21558