

113

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Menominee
(County)

Located In:

Corner Code ≠

- 1. Public Land Survey T 34N R 26W K-5.
 T _____ R _____
 T _____ R _____
 T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, David Babbitt, in a field survey on 10/23, 19 86, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

K-5. Northeast section corner of Section 14. Found no record of this corner since the original Gov't. survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-5. Found 1/2" rod with RLS cap bearing #26461 in line with the centerline of roads north and west. Witnessed as found.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- K-5. 1/2 Re-rod w/RLS cap.
- 6" h. maple N63W, 105.0'
- 3" w. birch N21E, 81.6'
- 4" w. birch S14E, 21.5'
- 6" h. maple S25W, 19.4'

Signed by David B. Babbitt

Date 1-27-87

Surveyor's Michigan License No. RLS 21558