

OK

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Menominee</u> <small>(County)</small>	Located In:	Corner Code ##
1. Public Land Survey	T <u>34N</u> R <u>26W</u>	<u>M-3, K-3.</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, David B. Babbitt, in a field survey on 8/13, 19 87, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

M-3. NE section corner of Section 12. Wood Post. Cedar 8", N60W, 14 Lks.
Cedar 12", S33W, 10 Lks.

K-3. NW section corner of Section 12. Wood Post. Beech 4, N40W, 15 Lks.
Sugar 14, S21E, 36 Lks.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-3. Set in § of E-W county road and in line with very old, abandoned road grade south.

K-3. Set in line with centerline of rds. east and south.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-3. DNR Monument.	K-3. DNR Monument.
9" cedar N53E, 55.8'	11" h.maple N50E, 36.7'
4" w.birch S41E, 55.6'	12" h.maple S70E, 84.2'
5" r.maple (in clump) N36W, 67.7'	6" h.maple S66W, 38.8'
9" tamarack S65E, 121.9'	6" h.maple N41W, 26.3'

Signed by David B. Babbitt

Date 2-9-88

Surveyor's Michigan License No. 21558