

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

Menominee  
(County)

Located In:

Corner Code ##

- |                                       |                           |                       |
|---------------------------------------|---------------------------|-----------------------|
| 1. Public Land Survey                 | T <u>34N</u> R <u>26W</u> | <u>K-4, L-4, L-3.</u> |
|                                       | T _____ R _____           | _____                 |
|                                       | T _____ R _____           | _____                 |
|                                       | T _____ R _____           | _____                 |
| 2. Property Controlling<br>in Section | S _____ T _____ R _____   | _____                 |
|                                       | S _____ T _____ R _____   | _____                 |
| 3. Miscellaneous<br>Property in Sec.  | S _____ T _____ R _____   | _____                 |
|                                       | S _____ T _____ R _____   | _____                 |

**Register of Deeds Stamp & File Number**

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, David B. Babbitt, in a field survey on 8/19, 19 87, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therofore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

- K-4. West 1/4 corner of Section 12. Wood Post. Beech 6, N36E, 23 lks.  
 Beech 6, N72W, 22 lks.  
 L-4. Center 1/4 corner of Section 12. No previous record.  
 L-3. N1/4 corner of Section 12. Wood Post. Hemlock 18, N75E, 28 lks.  
 DO 6, S10E, 08 lks.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

- K-4. Set in  $\frac{1}{2}$  of N-S county road and in line with very old fence west.  
 L-4. Set at the intersection of the N-S and E-W 1/4 lines of Section 12.  
 L-3. Set in line with centerline of rds. E-W and North.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

- |                             |                         |                         |
|-----------------------------|-------------------------|-------------------------|
| K-4. DNR Monument           | L-4. DNR Monument       | L-3. DNR Monument       |
| 5" sugar maple, N43E, 45.1' | 4" beech, S84E, 38.7'   | 11" r.maple N40E, 79.4' |
| 8" " , S59E, 40.2           | 3" y.birch, S27W, 36.5' | 3" cedar, S43E, 31.5    |
| 10" tw. " , N61W, 27.3      | 4" maple, N70W, 15.1'   | 6" hemlock, S01W, 34.0  |
| 5" basswood, S46W, 37.6     | 12" beech, N35W, 55.9'  | 9" " , S56W, 73.8       |

Signed by David B. Babbitt

Date 2-9-88

Surveyor's Michigan License No. 21558