

OK 1/15

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Menominee</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling In Section	S <u>12</u> T <u>34N</u> R <u>26W</u>	<u>7, 6, 13.</u>
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, David B. Babbitt, in a field survey on 1/6, 19 88, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 7. North 1/16 corner on East section line of Section 12. No previous record.
- 6. North East 1/16 corner of Section 12. No previous record.
- 13. SE 1/16 corner of Section 12. No previous record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- 7. Set MPOL between the East 1/4 corner and the NE section corner of Section 12.
- 6. Set at the center of the NE 1/4 of Section 12 by closed traverse.
- 13. Set at the center of the SE 1/4 of Section 12 by closed traverse.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- | | | |
|-----------------------------|----------------------|------------------------|
| 7. DNR Monument | 6. DNR Monument | 13. DNR Monument |
| 5" sugar maple, N19E, 27.4' | 5" cedar S65E, 50.0' | 9" cedar N40W, 9.2' |
| 10" y.birch, N77E, 5.1 | 9" cedar, S10E, 27.5 | 9" cedar N08E, 32.0 |
| 8" hemlock, S08W, 19.3 | 8" cedar, S70W, 15.5 | 8" cedar N50E, 27.7 |
| 4" y.birch, N60W, 5.9 | 4" cedar, N5W, 2.2 | 11" hemlock N84E, 20.5 |

Signed by David B. Babbitt

Date 2-9-88

Surveyor's Michigan License No. 21558