

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

<u>Menominee</u> <small>(County)</small>	Located in:	Corner Code #
1. Public Land Survey	T <u>34N</u> R <u>26W</u>	<u>H-13, G-13.</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S <u>34</u> T <u>34N</u> R <u>26W</u>	<u>15.</u>
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

**Register of Deeds Stamp & File Number**

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, David Babbitt, in a field survey of 12/6, 19 89, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therofore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

- H-13. South 1/4 corner of Section 34. Wood post. J.H. Mullett, DS, 1848. Cedar 6, N29E, 6 Lks. Cedar 10, N83W, 11 Lks.
- 15. West 1/16 corner on the south section line of Section 34. No previous record.
- G-13. Southwest section corner of Section 34. Wood post. J.H. Mullett, DS, 1848. Tam. 10, N84W, 38 Lks. Tan. 6, N22E, 21 Lks. Tam 12, S80E, 41 Lks. Tam. 8, S64W, 50 Lks.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

- H-13. Set MPOL between the SW and SE section corners of Section 34.
- 15. Set MPOL between the south 1/4 corner and the SW section corner of Section 34.
- G-13. Set by single proportion to the GIO record between the south 1/4 corner of Section 33 and the SE section corner of Section 34. Could not identify OBT's.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

- |                           |                               |                              |
|---------------------------|-------------------------------|------------------------------|
| H-13. DNR Monument.       | 15. DNR Monument.             | G-13. DNR Monument.          |
| 8" cedar, N36E, 18.15'    | 5" sugar maple, N42E, 26.2'   | 4" cedar, N20E, 8.9'         |
| 9" cedar, S37E, 5.15'     | 5" sugar maple, S42E, 30.1'   | 6" cedar, S61E, 19.35'       |
| 5" black ash, S29W, 23.6' | 13" sugar maple, S33W, 22.95' | 3" black spruce, S37W, 14.9' |
| 10" cedar, N53W, 6.5'     | 6" sugar maple, N34W, 32.9'   | 8" tamarack, N46W, 41.2'     |

Signed by David B. Babbitt Date 12-28-89  
 Surveyor's Michigan License No. 2158