

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Manominee</u> <small>(County)</small>	Located in:	Corner Code ##
1. Public Land Survey	T <u>34</u> R <u>26W</u>	<u>F-13.</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, David Babbitt, in a field survey on 12/5, 19 89, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules theretofore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

F-13. South one quarter corner of Section 33. Set 4" cedar post from Gov't. B.T. - Co. Surveyor Haas, May 22, 1900. Record in large ledger at Reg. of Deeds Office, no OBT's given.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

F-13. South 1/4 corner of Section 33. Description of Restoration Procedure: Set by retracing the section sub'n. of Sec. 33 by Co. Surveyor Haas dated May 22, 1900, which states "set 4" cedar post from Gov't. B.T.". I spent several hours searching for a post and OBT but could not identify either. There are many tam. stump remains but most are too rotted to show any marks. Single prop. to the GLO record does not fit the occupied lines in the north part of the section. Said occupied lines do, however, agree quite closely with the record of survey from 1900. While I have not found exact points (i.e. cor. mons.) for the center of section and 1/16 cors. indicated, I believe that the occupied lines are the result of the survey done in 1900 by Mr. Haas. I have, therefore, set this 1/4 cor., using an average comparative measurement from the north 1/4 cor., for the N-S position and projecting a line from the north 1/4 cor. across the occupied center of section for the E-W position. This position fits the swamp edge call 5.50 chains east from the original survey record very well and falls just south of an old E-W winter road as described to me by Mr. Ken Rasner Sr., long time local landowner, who says he saw a squared cedar

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner: post just south of said road years ago.

- F-13. DNR Monument.
 8" cedar, N07E, 9.2'
 4" cedar, S47E, 5.7'
 5" cedar, S52W, 24.6'
 5" cedar, N49W, 13.3'

Signed by David B. Babbitt Date 12-28-89
 Surveyor's Michigan License No. 21558