

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Menominee</u> <small>(County)</small>	Located in:	Corner Code <u>##</u>
1. Public Land Survey	T <u>34N</u> R <u>26W</u>	<u>I-12, I-13.</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	16		17		18		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, David Babbitt, in a field survey on 11/28, 19 89, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- I-12. West one quarter corner of Section 35. Wood post. J.H. Mullett, D.S. - 1848.
 Hemlock 12, N77W, 08 lks. Hemlock 6, S34E, 17 lks.
- I-13. Southwest section corner of Section 35. Wood post. J.H. Mullett, 1848.
 Maple 10, N67W, 22 lks.
 Cedar 10, N34E, 25 lks.
 Cedar 10, S48W, 11 lks.
 Hemlock 12, S28E, 34 lks.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- I-12. Set MPOL between the NW and SW section corners of Section 35. No original evidence found.
- I-13. Could not identify OBT's. There are some cedar stumps and blow downs in the area but most are in very poor condition. There are no discernable lines of occupation and single proportion to the original survey record does not fit nearby stream calls well at all. I have, therefore, set this monument to fit stream calls 330 ft. and 429 ft. east and 231 ft. north. Calls for leave swamp 3432 ft. west and enter swamp 4092 ft. west also fit this position well. This method, while somewhat arbitrary, puts the corner position closer to its original position than any other method available.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- | | |
|--|--|
| I-12. DNR Monument.
5" cedar, S48E, 22.1' | I-13. DNR Monument.
3" balsam, N21E, 13.85' |
| 5" cedar, S11E, 21.35' | 12" red maple, S10E, 27.75' |
| 6" black ash, S63W, 5.0' | 9" red maple, S61W, 49.4' |
| 5" cedar, N9W, 3.75' | 11" red maple, N54W, 29.65' |

Signed by David B. Babbitt Date 12-28-89
 Surveyor's Michigan License No. 2558