

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Menominee</u> (County)	Located in:	Corner Code #/
1. Public Land Survey	T <u>34</u> R <u>26W</u>	<u>I-10, I-11, J-10.</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2								
3													
4	7	8	9	10	11	12							
5													
6	15	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, David Babbitt, in a field survey of 11/21, 19 89, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- I-10. West one quarter corner of Section 26. Wood post. J.H. Mullett, D.S. - 1848. Tam. 8, S40W, 12 lks. Tam. 6, N59E, 18 lks.
- I-11. Southwest section corner of Section 26. Wood post. J.H. Mullett, D.S. - 1848. Cedar 12, N52W, 16 lks. Cedar 12, S4E, 22 lks.
- J-10. Center one quarter corner of Section 26. No previous record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- I-10. Set in $\frac{1}{2}$ of E-W county road at double the distance east from a fence north at the center of Section 27 to a fence north at the east 1/16 cor. of Section 27. This position fits exactly the call for a stream 10 and enter swamp 75 lks. south of the 1/4 corner. The stream has been blocked off by construction of the road and water no longer flows there but the bed is still evident although it is silting in and may not be very discernable at some future time.
- I-11. Set by double proportion to the GLO record using section corners 1 mile west, 1 mile east and 1 mile south and the 1/4 corner 1/2 mile north. No original evidence found.
- J-10. Set at the intersection of the N-S and E-W 1/4 lines of Section 26.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- | | | |
|---------------------------------------|-------------------------|-------------------------------|
| I-10. 1" iron pipe w/plastic RLS cap. | I-11. DNR Monument. | J-10. 1 1/2" iron pipe w/cap. |
| 7" cedar, N45E, 50.0' | 6" cedar, N39E, 36.0' | 4" cedar, N32E, 43.7' |
| 5" cedar, S25E, 48.4' | 7" y.birch, S45E, 35.9' | 6" cedar, S67E, 139.3' |
| 7" cedar, S35W, 57.0' | 5" cedar, S72W, 18.15' | power pole, S54W, 40.7' |
| 7" tamarack, N37W, 55.6' | 5" cedar, N25W, 14.6' | 6" cedar, N15W, 62.0' |

Signed by David B. Babbitt Date 12-28-89
 Surveyor's Michigan License No. 21558